

**SURVEY & REMONUMENTATION**

FILED

JUN 29 1995

VAN BUREN COUNTY REMONUMENTATION PROGRAM

FEB 13 10 29 AM '95

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COLUMBIA TWP.

Van Buren (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 13 T 1 S. R 15 W.	M-6
	E 1/2 Post T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS  
LIBER 4 PAGE 281  
7-00  
0213 0101 105URVEY  
712

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S., in a field survey on Feb. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

5/1827 Gov.: W. Broofield DS: N. on E. boundary Sec. 13. Left Lake at 6.81 ch (449.46') at old post on its N. margin at 40 ch set 1/4 Sec. post at 370 lks (244.20') S. of old one. Wit.: 7" Beech S58°W 14 lks (9.24'), 8" Sugar Maple N58°W 10 lks (6.60'). 4/1869 AJ Pierce CS: Bk. 3 p.64-65: Witness trees gone; road work & filled here; chained from N 1/4 post & planted corner stake & several stones; meas. to NE cor. 2624.16' & W. to Center 2624.82'. 8/1/1904 VH Todd CS: Red Bk., fd. stake & stones; wit.: 8" Maple SE 60 lks (39.60'), 11" Sycamore NE 91 lks (60.06'). 9/21/1905 WH Goss CS, Field Bk.: Fd. stake & stones 97 lks. (64.02') S. of Bloomingdale corner; same wit. as Todd. 7/25/1933 TA Smith CS: Red Bk., Meas. from NE cor. to E 1/2 post: 2627.4'. 1964 WJ Smith CS: Sec. sheet shows distance from E 1/2 post to Center as 2637.30'. 12/18/1994 JC Hunt PS: Work sheet shows + distance from E 1/2 post to Center as 2634.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-6 East Quarter Post of Section 13 T1S-R15W, Columbia Township.  
Corner evidence found: Several small stones--no stake. (Dug through 8" asphalt road surfacing 64.02' South of W 1/2 Post Bloomingdale Twp.--record Gov. jog; then dug hole & found several small stones approximately 4' below surface.) Set Harrison Marker & monument box at 64.02' South of said W 1/2 Post & on line with NE corner of Sec. 13 T1S-R15W, in line with old woven wire fence to West. Corner is 6.5' East of centerline of road.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JANUARY 25, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**M-6 HARRISON MARKER IN MONUMENT BOX**

West 33.40' Nail & Tag in top of wood post on N. side of conc. post.  
S.42°W. 50.56' Set nail & washer in N. face of pole.  
S.69°E. 51.42' Nail & tag in W. face of 12" dia. tree.  
N.21°W. 100.98' Found nail in SW face wood post by telephone cable box.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 2/13/95 D. R. G.

Signed by John C. Hunt  
Surveyor's Michigan License No. 23513

Date Feb. 8, 1995

