

NOV 15 1994

LIBER 4 PAGE 172

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Mark A. Smith  
VAN BUREN CO  
REGISTER OF DEEDS

For corners in Geneva Township

Van Buren County  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R16 W 8-E  
     E 1/4 Post Sec 20 T \_\_\_\_\_ R \_\_\_\_\_  
                           T \_\_\_\_\_ R \_\_\_\_\_  
                           T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section          S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.  S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

7-00  
0101 10SURVEY  
10/18

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald R. Gilchrist, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Government - 1830 - Set 1/4 Post on a 17" Hemlock
- A.J. Pierce, Co. Surveyor (3/23/1871) - Div Sec Rec - Found Gov't cor (4-55)
- W.H. Goss, Co. Surveyor - (10/3004) - Fd stone & crockery - 2 1/2" Maple - N 86° E - 27'
- T.A. Smith, Co. Surveyor (9/24/48) - Note: Showes Corner.
- D.R. Gilchrist, Co. Surveyor (10/12/78, 10/18/78, 11/28/78, 3/5/92). Rec Survey (8-164) P.P. - S 45° W - 62.26'; 8" Twin Ch - S 80° E - 64.59"; 20" Maple - N 30° E - 126.06'.
- G. Mitchell (1978) - Fd. re-bar. Same wit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fd. 1/2" Iron (bent) Tied Off, Dug Down 1', Found 1/2" pipe in cast iron ring.
- Set 1' Section of Harrison Marker over top.
- P.K. Nail - N 1.05
- P.K. Nail - E 1.0

Corner was field checked on 9/26/94 by D.R. Gilchrist, Co. Surveyor.  
 Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Harrison Marker
- Iron 33' West
- 2' W CL Rd
- P.P. - S 45° W - 64.07' Nails. Side
- Twin 8" CH - S 75° E - 64.57' Nail S side
- 6" Cedar - N 40° E - 64.99' Nail N side
- 10" Tree of Haven - S 55° W - 52.83' Nail NW side

Ratified by Peer Group in accordance with P.A. 345 of 1998  
 Van Buren County Surveyor

Date D.R.A. 10/18/94

Signed by Donald R. Gilchrist Date 10/3/94  
 Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

