

FILED

99-19395
L5R1-16.tff

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 16 9 40 PM '99

For corners in GENEVA
VAN BUREN

Mark A. Smith
VAN BUREN CO
REGISTER OF DEEDS

Located In: Corner Code #

- 1. Public Land Survey T1S R16W L-5
S $\frac{1}{4}$ post Sec. 12
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S T R
in Section S T R
S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S T R
Property in Sec. S T R
S _____ T _____ R _____

DEC 28 1999

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John C. Hunt, P.S. Nov. 16, 99
I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5 4/18/30 GOVERNMENT K. Clark, D.S.: Corrected West 39.555 chs. (2610.63') & set quarter Sec. post. 4/15/1952 T.A. Smith, C.S.: Sec. 12. Note shows quarter post. Distance North is 1319.12', and continuing North 1319.12' to center quarter post, and continuing North 1317.00', and continuing North 1317.00' to North quarter post for a total of 5272.24'. 6/2/1995 G.J. Mitchell, P.S.: Sec. 12. Rec. survey (L.1127 p.812). Found rebar in centerline of road. Wit.: 34" Maple East 37.32'; 28" Maple SSE 124.27'; Power Pole NNW 101.60'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 South Quarter Post Sec. 12, T1S-R16W Geneva Twp., Van Buren Co., MI :

Found 1/2" I.R. in centerline of gravel road. Removed 1/2" I.R. and set Harrison Marker in mon box. This corner is the same corner as shown on survey recorded in L.1127 p.812 of Surveys. Measured N00°00'41"E 5269.06' to North Quarter Post of Sec. 12-1-16. Measured S89°53'08"W 2596.665' to SW corner of Sec. 12-1-16.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON OCTOBER 6, 1999, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12-15-99 *D. R. G.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 HARRISON MARKER IN MON BOX

N87°E 37.36' Found nail in Southwesterly base of 36" Maple.
N16°W 101.60' Found nail in West face of pole.
S16°E 124.17' Found nail in West face of 30" Maple.
N70°W 31.20' centerline of telephone cable box.



Signed by *John C. Hunt, P.S.* Date Dec 9, 1999
Surveyor's Michigan License No. 23513