

JAN 14 1998

VAN BUREN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 16 12 00-PM '97

SECTION

For corners in VAN BUREN COUNTY Located in: GENEVA TWP. NE COR. SEC 24 T1S,R16W Corner ID #

Mark A. Smith VAN BUREN COUNTY REGISTERED SURVEYOR

- 1. Public Land Survey T 1S R 16W M-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Liber 5 Page 44

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, Alan Bartlett in a field survey on November 25 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(PLEASE SEE BACK OF PAGE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN MONUMENT BOX 11' NORTH OF CENTER LINE OF EW ROAD VERIFIED CORNER LOCATION USING EXISTING WITNESSES. THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS NOVEMBER 19 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 1/2" DIAMETER HARRISON MONUMENT IN MONUMENT BOX 11' NORTH OF CENTER LINE OF EW ROAD

- WITNESSES
N60°E 47.34' P.K. NAIL IN WEST SIDE OF 5' POLE
N62°E 46.72' CL OF TELEPHONE RISER BOX
S30°E 79.67' CL OF TELEPHONE RISER BOX
S42°W 67.16' CL OF TELEPHONE RISER BOX
N20°W 73.27' DBL HEADED NAIL IN W. SIDE OF P.P.
SOUTH 27.06' A-7 SW CORNER OF SEC 18 T1S, R15W

CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D. R. A. 12/16/97



Signed by Alan B. Bartlett Date 12/15/97 Michigan License No. 35988

Surveyor's

M-7 T1S,R16W

*LIBER 5 PAGE 45*

1827 GLO BROOKFIELD  
NORTH ON EAST BOUNDARY OF SECTION 24  
80.00 SET COR. POST TO SEC 1 3 & 24

10/2/90 JOHN C. HUNT RLS#23513 LCRC LIBER 3 PAGE 172  
FOUND 1" IRON PIPE IN CENTERLINE OF COUNTY ROAD 681 N&S CENTERLINE OF COUNTY ROAD 384 IS  
12' SOUTH

	WITNESSES	
SOUTH 27.06'	FOUND 1" PIPE FOR N.W. CORNER OF SECTION 19 T1S, R15W	
N20° W	73.20'	FND NAIL IN WLY FACE OF POLE
N50° E	47.15'	FND NAIL IN SLY FACE OF POLE
S40° W	67.30'	C/L OF TEL. CABLE BOX
S35° E	79.50'	C/L OF TEL. CABLE BOX

4/28/93 DONALD GILCHRIST RLS# 13583  
FOUND 3/4" PIPE (BENT)

	WITNESSES	
POWER POLE N30° W	73.15'	
CABLE RISER N45° E	46.55'	
CABLE RISER N45° E	79.52'	
CABLE RISER S40° W	67.20'	

11/17/1997 LANDMARK TECH. ALAN BARTLETT RLS# 35988  
FOUND 3/4" IRON PIPE IN MONUMENT BOX 11' NORTH OF CENTER LINE OF E/W ROAD

	WITNESSES	
N60°E 47.34'	P.K. NAIL WEST SIDE OF 5' POLE	
N62°E 46.72'	CL OF TELEPHONE RISER BOX	
S30°E 79.67'	" " " "	
S42°W 67.16'	" " " "	
N20°W 73.27'	DBL HEADED NAIL IN W.SIDE P.P.	
SOUTH 27.06'	A-7 SW CORNER OF SECTION 18	