APR 2 5 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Dec 28 2 24 PH '91

Fo	SOUTH HAVEN VAN BUREN County			Corner Code ≠#		YMark Concly							
1.	Public Land Survey SW COR SEC-11	T T	R <u>=17W</u> R R	I-5									
2.	Property Controlling in Section	S T S T	R R R										
3.	Miscellaneous Property in Sec.	S T S T	_ R		Registo	er of l	Deeds	Star	np &	File	Nun	nber	r ——
4.	Lot No,	Recorded Plat				A B	C D	E	F G	н	l J	ĸ	L
Э.	Private Claims					6-	5-		1	3-		\Box	Ţ
					3		++		1	Ţ	١Ī	\perp	_
					4	/ 7_	_ _ _a .		9	-10—	ļ.,,	,	12-
in I cui Ma aba Coi exp	I. BASTL ANDRESS, in a field survey on DECEMBER 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:						29	2	1	-22	23	3	-13 -24 -25
NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.						31-	-32-	3	3	34—	35	-	-36
A.	2/1830 - GOVERN RAN NORTH BETWE WITNESSES: 7" 19" DIST WEST OF 80 DIST EAST OF 80	MENT - ROBERT EN SECTIONS 14 BEECH N 16DEG HEMLOCK S 11 0.00 CHS 0.16 CHS (5290.	CLARK, JR. & 15 A D -15' W 5 DEG E 4 56')	ISTANCE OF 80.00 CHS 52 LKS (34.32')		Rai scord: Van	ST CO tilled by ance wi Buren	y Peei th P.A Count	Group 1. 345 y Surve	of 19 eyer			-
	6/13/1869 - A. BOOK-3, P-79 SOUTH PART OF S	,				. 2,	1601	77	<u>, w</u>	<i>(</i> /,	المكر	4	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1/2" IRON IN MON BOX.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE THE POSITION OF THE ORIGINAL CORNER.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS. 10-5-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" IRON W/ HARRISON MONUMENT.

FD. PK NE SDE PP N 35 W 55.17 PK & TAG NW SDE 30" PINE S 60 W NW COR CONC BLK FND N 40 E 114.75 FD. PK SW SDE PP S 55 E 51.61' PK & TAG SSW SDE 32" PINE N 65 W 112.98' C/L BAILEY AVE (M-43) WEST 1.3' C/L AYLWORTH AVE NORTH 1'

BASIL J.
ANDRESS, JR.
PROFESSIONAL
SURVEYOR
No.
30075

Signed by _____ Surveyor's Michigan License No.

ZG DEC 94

9536 12/28 FOREO APRILO CENTRALE HAN STATE GRAND OF LAND SURVEYORS, JAN. ; REVISED MAY REVISED JA

SHEET 1 OF 2

CONTINUED FROM FRONT OF CERTIFICATE

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

```
9/1871 - BOOK-4, P-73 (SEC-10)
CORNER - ROOTS OF STUMP REMAIN - STAKE PRESENT-RENEWED.
WITNESSES: 5" SUGAR MAPLE N 44DEG W 61.5 LKS (40.59')
            6" SUGAR MAPLE N 28DEG E
                                        84.5 LKS (55.77')
DIST WEST 19.94 CHS (1316.04') TO 1/8 POST, AND CONT. WEST 19.94 CHS TO 4 POST (2632.08') DIST NORTH 9.97 CHS (658.02'), AND CONT. NORTH 9.97 CHS TO 1/8 POST (1316.04')
3/1872 - BOOK-4, P-93 (SEC-14)
ROOTS OF HEMLOCK WITNESS REMAINS - SET STAKE - SEE P-73.
8/1873 - BOOK-4, P-155 (SEC-11)
SAME AS ABOVE. DIST EAST 39.97 CHS (2638.02')
11/18/1919 - WARREN H. GOSS, C.S.
RED BOOK (SEC-14)
3/4" PIPE - 6" EAST & 8" SOUTH OF C/L OF SOUTH END CONC. PAVEMENT.
12/2/1919 - RED BOOK (SEC-15)
STONE
WITNESSES: 12" MAPLE NW
                            40 '
            14" MAPLE STUMP NE
                                   י חצ
10/26/1926 - T. A. SMITH, C.S.
SEC-10
            SEC COR 0.98' S & 1.0' E OF AXLE SET BY HIGHWAY DEPT.
            DIST WEST OF 1316.5' TO 1/8 POST, AND CONT. WEST 1316.5' TO 4 POST
            DIST NORTH OF 1316.6' TO 1/8 POST, AND CONT. NORTH 1316.6' TO 4 POST
            DIST BY GOSS - EAST 2643.5' TO 4 POST
            ANGLE (T. A. SMITH) NORTH TO EAST OF 88DEG-29'-30"
            9/6/1935 - (T. A. SMITH)
    DIST EAST OF 1321.5' TO 1/8 POST, AND CONT. EAST 1321.5' TO 4 POST
            1930+/- (SEC-15)
            DIST EAST OF 1315.9' TO 1/8 POST, AND CONT. EAST 1315.9' TO 1/4 POST
            DIST SOUTH OF 1316.4' TO 1/8 POST, AND CONT. SOUTH 1316.4' TO \frac{1}{4} POST
            ANGLE FROM EAST TO SOUTH =89DEG-32'
            6/19/1942 - DRAWING SHOWS CORNER
            ANGLE FROM NORTH TO EAST = 88DEG-29'-30"
            4/1948 - DRAWING SHOWS CORNER
            DIST WEST IS 658.25'
            DIST NORTH IS 329.15'
            5/1959 - MON BOX IN C/L OF M-43 (MSHD)
4/4/1952 - W. Q. SMITH, C.S.
DRAWING SHOWS CORNER
7/2/1972 - D. A. RATEKIN, R.L.S.
RECORDED SURVEY L-2, P-191
1/2" IRON IN MON BOX W/ WITNESSES
L.C.R.C. L-2, P-84
IRON IS 1.3' EAST & 1' SOUTH OF C/L "X"
DIST EAST IS 2642.28'
10/13/1977 - DON R. GILCHRIST, C.S.
RECORDED SURVEY L-7, P-148 & 149
MEAS WEST 1316.48' TO POINT SAID TO BE 1/8 POST, AND CONT. WEST 1316.08' TO ₺ POST
7/7/1978 - RECORDED SURVEY L-8, P-161
DIST WEST OF 1316.48' AND 1316.08'
9/14/1982 - DANIEL B. ZWAR, L.S.
RECORDED SURVEY L-9, P-23 & 24
SHOWS CORNER
```

Liker 4 page 215