

**SURVEY & REMONUMENTATION**

FILED

SEP 18 1997

MAR 27 8 42 AM '97

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

**S.W. COR., SEC. 32**  
For corners in Almena Township

Filing Requirement of Act 74, Mich. P.A. 1970

*Mark A. Smith*  
VAN BUREN CO.  
REGISTERED PROFESSIONAL SURVEYOR

Van Buren Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>2S</u>	R	<u>13W.</u>	<u>C-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

*Liber 4 page 494*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on January 31, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1827 - William Brookfield, D.S., Set Post corner for Sections 31 and 32, 11" Wh. Oak N. 33° E. 135 lks. (89.10'), 10" Wh. Oak N. 35° W. 105 lks. (69.30')  
1829 - William Brookfield, D.S., (For Survey of Antwerp Twp.) "Intersected North Boundary 213 lks. (140.58') East of Post" (said Post being SW cor., Sec. 32, Almena Twp.)

1972 - Smith & Smith, Inc., L.C.R.C. L. 1, Pg. 554, "Set 1/2" iron bar on quarter Section breakdown and government distance from Antwerp corner". 60d spike in SE side 36" Oak S.W. 17.12', 60d spike in SE side 40" Oak N.E. 58.00'. Corner is 18'± South centerline of road.

1978 - Gove Associates, Inc., Found rered 6" down, Power pole Northwesterly 50.28' to tack and washer, 40" Oak Northeasterly 59.14' to tack and washer, 36" Oak Southwesterly 16.40' to tack and washer, Corner is 15± South centerline road.

1980 - Alpha Engineering, Inc., 1/2" Iron Bar, 36" Oak S. 60° W., 16.41', 40" Oak N. 20° E. 57.69', Centerline road North 18'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found iron bar 18' South of centerline East and West Road and 140.7'± West of Antwerp Township corner. Found iron bar also matches 1980 witnesses to both oaks. Location of found iron bar was ratified by the Van Buren County Remonumentation Peer Group on January 29, 1997.

THIS TRANSFER MADE BY  
MARK A. SMITH  
REGISTER OF DEEDS  
VAN BUREN COUNTY

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 3/27/97 *D. R. G.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

The location of found iron bar is accepted as the best available evidence of the position of the original corner. Replaced found iron bar with a standard Van Buren County Remonumentation monument with monument box over, Accessories:

- "PK" Nail in Southeasterly side 40" Oak N. 20° E. 58.65'
- "PK" Nail in Southeasterly side 36" Oak S. 60° W. 16.68'
- "PK" Nail in Easterly side utility pole N. 15° W. 62.11'
- "PK" Nail in Northerly side utility pole S. 80° E. 114.75'



Signed by *Allen H. McMachen*  
Surveyor's Michigan License No. 16935

Date 2/10/97