

SURVEY & REMONUMENTATION

FILED

1993

JAN 11 4 49 PM '94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mark A. Smith
 VAN BUREN CO.
 REGISTER OF DEEDS

For corners in **ALMENA TWP.**

<u>VAN BUREN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> R <u>13</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Allen H. McMachen, a field survey on November 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - G. Harrison D.S. ran North between Section 27 & 28 and set corner post, accessories: 5" W. Oak N. 21 deg. W. 15 Lks; 4" W. Oak N. 37 deg. E. 22 Lks. 1898 - C. Mutchler C.S. found stake after being told by local resident, of 40 to 50 years, where to look. Mutchler measured North 2659.14' to quarter cor. 1948 - T.A. Smith C.S. measured 2567.0 feet between S.E. cor. & S. 1/4 cor. of Sec. 21.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner or accessories not recovered. Found 1/2" (I.D.) pipe as referenced in Surveys recorded: L.2, P.13; L.3, P.48 & P. 205; L.7, P.112 & P.194. Recent measures indicate S.W. Cor. Sec. 22 to W. 1/4 cor. at 2659.88 feet and S.E. cor. Sec. 21 to S. 1/4 cor. at 2568.09 feet. Found pipe was ratified by Van Buren County Remonumentation Peer Group on Nov. 17, 1993 and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Dug and removed existing 1/2" pipe, found no additional evidence of a corner down to 30" deep. Placed standard 30" Harrison Monument. Witnessed by: Nail in West face 10" Oak NORTH 54.92'; Nail in West face 18" Oak S. 10 deg. E. 16.65'; Nail in West face 18" Oak S. 5 deg. E. 37.50'; Nail in South face West branch twin 15" Cherry N. 80 deg. W. 59.00.

Signed by Allen H. McMachen 16935 / 94
 Surveyor's Michigan License No. _____
 State of Michigan Registered Land Surveyor No. 16935
 Liber 4 Page 126
 APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 10 SURVEY 7.00