

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Mark A. Smith  
VAN BUREN CO.  
REGISTER OF DEEDS

LIBER 4 REVISION

For corners in Almena Township

Van Buren County  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 13W I-3  
NW Corner Sec 11 T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald R. Gilchrist, in a field survey on June 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Gov't - Set post corner; 6" Beech S 85° E 24 lk; 8" Beech S 70° W 40 lk. A.J. Teed (1874) Fd stake & stumps of both Wit, set new stake. Geo. Mutchler (1901) set skein iron by meas. W.V. Ackley (1912) Fd pipe & brick. T.A. Smith (1945) Fd wagon skein. W.Q. Smith (1960) set pipe (wrong). S&S (1971) Fd wagon skein, Also Fd 3/4" pipe Sw 6.43' Recorded Liber 1, Page 150.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Fd. Wagon Skein as Recorded in Liber 1, Page 150, laying at 45° (straightened). Set Harrison Marker in place of above. Corner approved at Peer Group Meeting on 5/20/92, recorded Liber 3, Pages 240 & 241. Corner was field checked on 6/22/94 by D.R. Gilchrist, County Surveyor. Approved at the 6/29/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date D. R. G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker  
P.P. S 22°21' E 91.85' nail W side  
20" W Ch N 89°00' W 58.58'  
18" W Oak S 64°54' W 64.69' nail SE side  
8" W Oak S 46°26' W 75.67' nail S side  
15'± E of CL Rd  
130'± of CL Rd to West  
Set Sur. marker sign post 6' East



Signed by Donald R. Gilchrist

Date 9/22/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583