

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 10 8 24 AM '96

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS

For corners in Waverly Township  
Van Buren County  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 2S R 14W B-5  
S 1/4 Post Sec 7 T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Donald R. Gilchrist, in a field survey on November 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

**1827 - GOVERNMENT - William Brookfield, D.S.**

West between Sections 7 & 18 a distance of 74.30 chs (4903.80') and intersected West boundary 87 lks (57.42') North of Post. Set Post at intersection corner to Sections 7 & 18.

Witnesses:

Willow 5" - S 32 Deg E - 44 lks (29.04')

Willow 4" - N 20 Deg E 19 lks (12.54')

(Continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron in Mon Box - Raised Mon Box - Set Harrison Marker over iron.  
Distance West = 4903.94'.

Approved at the 10/25/95 meeting of the Van Buren County Peer Group and is accepted as the best available evidence of the position of the original corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 12/19/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker in Mon Box.

16" Wal - N - 79.59' N & W in W side.

Sign Post - N 76 Deg W - 64.56' to CL

16" Ch Elm - S 48 Deg W - 69.79' N & W - N side.

24" Wal - S - 64.22' N & W - W side

CL M-43 S 12'+-.



Signed by Donald R. Gilchrist  
Surveyor's Michigan License No. RLS 13583

Date 12/2/96

**1949 - M.D.O.T. Right of Way Book.**

Shows Corner to be 10.25' North of Centerline of M-43 Highway.

**10/18/95 - D. R. Gilchrist, C.S.**

Found Monument Box and 3/4" Iron.

*LIBER 4 PAGE 390*