

NOV 15 1994

FILED

LIBER 4 PAGE 153

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Oct 18 12 02 PM '94
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Waverly Township

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

9-00

Van Buren County Located In: Corner Code #

- 1. Public Land Survey T 2S R 14W D-3
S 1/4 Post Sec 5 T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

10/18 0101 10SURVEY

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald R. Gilchrist, in a field survey on September 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Gov 6" dia ironwood 40.15 ch to sec. cor. No wit. On Jan 28, 1868, C.D. Lawton - Co. Surveyor, noted could be stake or stone. Wit: Elm S 1/4° E 70 lks. Govt: 2649.90'/2649.90'; Lawton: 2647.26'/2647.26'; W.Q. Smith: 2657.44'/2655.42'. On May 11, 1962, Louis Zubak of MDOT searched for but unable to find cor. He placed 1" pipe midway bet ROW fences in line w/ N&S 1/4 line fence. On Nove. 9, 1971, W.Q. Smith, CS, found 1" iron bar. Wit: power pole w/ tack & washer N 65° E 157.94'; 16" pine S 65° W 66.11'; 15" (continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner was field checked on 9/26/94 by D.R. Gilchrist, Co. Surveyor, found corner just newly paved over - down 8". Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

On 10/13/94 D.R. Gilchrist placed a monument box over corner and raised with 6" extension.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date D.R.G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker down 8" under new paving. Placed Monument Box over. Iron rod w/cap #623 South 33.00' N 04° E 84.97' nail & tag E. face pole S 40° W 56.22' nail & tag E. face pole On CL Rd E & W

Signed by _____ Date _____

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

LIBER 4 PAGE 154

A. Continued from front of Certificate

pine S 60° W 54.26'. Corner recorded in Liber 1, page 174. Found corner as recorded in 1978, 1984, and 1988. On Oct. 23, 1992 found 1" iron bar noted by W.Q. Smith in 1971. Removed iron bar & set Harrison Marker in place, 6" below existing grade. All of Smith's witnesses gone except for power pole.