

JAN 14 1998

RECORDED

#97-17714 SECTION  
K6R13-2-14

VAN BUREN COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 17 2 25 PM '97

For corners in Waverly Twp.

Van Buren (County)	Located In:	Corner Code #
1. Public Land Survey W $\frac{1}{4}$ Post Sec. 13	T 2S R 14W	K-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Mark A. Smith  
VAN BUREN CO.  
SURVEYOR

LIBER 4 PAGE 500

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, John C. Hunt, P.S., in a field survey on July 22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4/1830 Government: G.W. Harrison, DS: Ran North between sections 13 & 14 a distance of 40.00 chs. & set quarter section post at edge of swamp.  
Witnesses:  
10" Red Oak N54°? 27 lks. (17.82')  
8" Ironwood S48°W 10 lks. (6.60')

Ratified by Peer Group in accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 10/17/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 West Quarter Post Sec. 13 (corner common to Sections 13 & 14) T2S-R14W, Waverly Twp., Van Buren Co., Michigan. (Note: NW corner of Sec. 13 not found. Held witnesses from prior survey.)  
Found wood anchor post rotted off for fence North, South, & East. Set Harrison Marker with witness post.

W $\frac{1}{4}$  Post is 2.65' South & 0.24' West of straight line & split of the mile. Measured South 2644.86' and measured North 2639.56' to approximate NW corner of section.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 25, 1997, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 HARRISON MARKER WITH WITNESS POST  
N16°E, 13.42', Set mag nail & washer in SW root of 26" Maple tree.  
N45°W, 30.50', Set mag nail & washer in East face of 17" Maple tree.  
S56°E, 33.25', Set mag nail & washer in North face of 14" Elm tree.  
S46°W, 38.45', Set mag nail & washer in East root of clump of Maple trees.



Signed by John C. Hunt Date October 9, 1997  
Surveyor's Michigan License No. 23513