

Van Buren County Remonumentation Program Dec 20 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Center of Section 22

For corners in Arlington Township

Mark A. Smith
VAN BUREN CO.
REGISTERED PROFESSIONAL SURVEYOR

7.00

Table with columns: Van Buren (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Liber 4 PAGE 483

Register of Deeds Stamp & File Number

412 12/20 0101 10SURVEY

I, Gary C. Bilow, in a field survey on 5/28, 19 93 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (8, H) contains the number 22.

A. Description of original monument and accessories and/or subsequent restoration: Post not established by original government survey. Found no records of corner ever being established.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12/20/96 D. R. G.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1-1/2" Well Point at the intersection of old downed fences projecting 1.5' above ground. Well Point is 2' North and 5' East of the calculated 1/4 line intersection. Accepted Well Point as the corner.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTAION PEER GROUP OF SURVEYORS AT A MEETING HELD OCTOBER 9, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Replaced Well Point with Harrison Monument on 12/19/96

- S73°E 6.64', Nail & Tag in 10" Maple
S2°W 25.89', Nail & Tag in 8" Maple
N66°W 29.34', Nail & Tag in 8" Beech
N15°W 31.99', Nail & Tag in 15" Beech



Signed by Gary C. Bilow
Surveyor's Michigan License No. 26453

Date December 19, 1996