

Van Buren County Remonumentation Program Dec 20 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Quarter Corner 22, 23

For corners in Arlington Township

Form with fields for County (Van Buren), Located In, Corner Code #, and survey types (Public Land Survey, Property Controlling, etc.)

Handwritten signature: Mark A. Smith

7-00

12/20 0101 10SURVEY

Handwritten: Liber 4 Page 486

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Gary C. Bilow, in a field survey on 5/28, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column H and row 8.

A. Description of original monument and accessories and/or subsequent restoration:

Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories: Sugar 13 N37W 4 links and Sugar 13 N54E 9 links. E.Stefan (PS #13599) recorded on a Act 132 Survey recorded in 1972 in Liber 1 Page 268 "RR spike - accessories: N70W 26.2' Iron pipe, S45E 50.6' Face 30" tree stump, N18E 98.73' Face of Telephone Pole, and Fence on line West."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike and two (2) of Stefan's accessories. Distances to adjacent corners were reasonable and consistent. Accepted RR spike as the best evidence of the original GLO post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTAION PEER GROUP OF SURVEYORS AT A MEETING HELD OCTOBER 9, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced RR spike with Harrison Monument on 12/19/96

- N73°W 26.1' Iron pipe
S35°E 50.6' Face 30" tree stump
West 33.00' DNR monument
East 2.0' centerline 50th Street
North 6.0' centerline 38th Avenue



Signed by Gary C. Bilow
Surveyor's Michigan License No. 26453

Date December 19, 1996