

Van Buren County Remonumentation Program Dec 20 2 47 PM '96  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Quarter Corner 15,22

For corners in Arlington Township

*Mark A. Smith*  
VAN BUREN CO.  
REGISTERED SURVEYOR

Van Buren (County)	Located in:	Corner Code #
1. Public Land Survey	T2S R15W	H7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Liber 4 PAGE 488*  
Register of Deeds Stamp & File Number  
12/20 0101 10SURVEY

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on 4/21, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories: Tamarack 10 N11E 17 links and Tamarack 12 S13E 10 links. A. Howard (PS #2382) recorded on a Act 132 Survey recorded in Liber 2 Page 255 "Iron Rod - accessories: N45W 4.5' 5" Maple, S30W 14.0' 10" Maple, West 44.73' 12" Maple."

Ratified by Peer Group in  
accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 12/20/96 *S. R. A.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron Pipe and none of Howards accessories. Distances to adjacent corners were consistent with Howards survey. Accepted this Iron Pipe as the best evidence as the original GLO post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTAION PEER GROUP OF SURVEYORS AT A MEETING HELD SEPTEMBER 25, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced 1" Iron Pipe with Harrison Monument on 12/19/96

N17°E	13.46'	Nail & Tag in 7" Ash
N56°E	4.46'	Nail & Tag in 6" Maple
S32°W	14.00'	Nail & Tag in 8" Maple
N23°W	14.59'	Nail & Tag in 5" Maple



Signed by Gary C. Bilow  
Surveyor's Michigan License No. 26453

Date December 19, 1996