

FILED

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 10 00 AM '93

For corners in  
Van Buren County  
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 2S. R 15W. D 5  
S. 1/4 Post Section 8 T R  
Arlington Township T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

*Mark A. Smith*  
VAN BUREN CO  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel B. Rahilly, in a field survey on 12/21/93, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1/30/1830 - GOVERNMENT SURVEY - George W. Harrison, D.S.  
Set 1/4 Sec. Post at 40.25 Ch.  
5" Beach - N. 76 Deg. E. - 3 lks.  
20" Elm - n. 89 Deg. W. - 20 lks.
- 11/15/1868 - A. J. Pierce, D.C.S.  
Set walnut Stake renewed, Stone previously set - one witness tree stump remains.  
Meas. West 2651.55' - Meas. East 2650.56'  
(A is continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Square Iron (Buggy Axle) Top bent 0.3' East  
Set Harrison Marker

Approved at 10/27/1993 Van Buren County Peer Group Meeting and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Harrison Marker
- 23" Pine S. 25 Deg. E. 30.92' to nail W. side
- 23" Cottonwood S. 80 Deg. W. 43.15' to nail N. side
- 13" Walnut N. 55 Deg. W. 36.80' to nail S. side
- 27" Maple N. 60 Deg. E. 49.30' to nail S. side



*Daniel B. Rahilly*  
Daniel B. Rahilly

Signed by \_\_\_\_\_ Date 12/21/93

Surveyor's Michigan License No. 22441

6620 12/27 01:05 10 SURVEY 9:00  
Liber 4 Page 113

- 4/20/1893 - W. H. Goss, C.S.  
Not Found, ranged line from fence.
- 8/23/1918 - "Red Book" - Set Buggy Axle, Set on line Center 1/4 & S. 1/8 Post.  
8" Spruce - S. 24 Deg. 30" E. 0.46 Ch. (30.4')  
12" Apple - N. 46 Deg. 30' E. 0.65 Ch. (42.9')  
3" Sugar - S. 53 Deg. 30' W. 0.54 Ch. (35.6')  
Shown in Red Book - Meas. N. 1323.96' & 1323.96' to Center 1/4 Post.  
W.H.G. note shows N. 1312.74' & 1312.74' Center 1/4 Post.
- 6/27/1940 - T.A. Smith, C.S.  
Found Axle Shaft - 18" Walnut S. 5 Deg. W. 35.5' (Cen. Line)
- 7/23/1969 - W.Q. Smith, C.S. - J. Boynton, P.S.  
Found Square Iron  
T.P. N. 10 Deg. E. 28.71  
18" Maple N. 50 Deg. E. 50.0'  
18" Pine S. 15 Deg. E. 30.70'
- 11/07/1969 - D.A. Rateken, R.L.S.  
Found 3/4" Solid Bar  
Meas. W. 2662.57' to Corner  
Meas. E. 2653.77' to Corner  
Computed Dist. N. to intersection of 1/4 Line 2643.68'
- 7/28/1972 - D.A. Rateken, R.L.S. - Rec'd in (L1-P524)  
Found 3/4" Solid Bar (Fence to S. 5' W.)  
Center Line Road 2' N. (Gravel)  
NW Cor. House S. 40 Deg. E. 80.60'  
24" Pine S. 35 Deg. E. 29.75'  
18" Maple N. 60 Deg. E. 48.95'