

MAY 18 1997

Van Buren County Remonumentation Program Dec 20 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Section Corner 21,22,27,28

For corners in Arlington Township

Mark A. Smith
VAN BUREN CO
REGISTERED SURVEYOR

7-00

411 12/20 0101 10SURVEY

Van Buren
(County)

Located in:

Corner Code #

1. Public Land Survey

T 2S R 15W G9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section

S _____ T _____ R 12/20/96 S.A.S. Date

3. Miscellaneous Property in Sec.

S _____ T _____ R VAN BUREN COUNTY SURVEYOR
S _____ T _____ R REGISTERED WITH P.A. 345 OF 1996
Ratified by Peer Group in _____

Liber 4 Page 490

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary C. Bilow, in a field survey on 5/28, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories: Beech 24 S44E 39 links and Elm 26 N65W 36 links. County Surveyor A.J. Pierce in 1870 in Volume 4 Page 33 "Found old stake set probably by C.J. Monroe - wits agreed." John Hunt (PS #23513) recorded an Act 74 Record in 1977 in Liber 2 Page 493 "Found 1/2" iron rod - accessories: NW 53.1' Nail & Washer in 16" Maple, SE 33.25' Street Sign Post, and SE 79.7' Nail & Washer in 6" Pine." George Mitchell (PS #19618) performed an unrecorded Act 132 Survey in 1980 noting "Found 3/4" pipe - accessories: NW 53.1' Stump, SE 35.5' Street Sign, WSW 51.4' Stop Sign, and West 5.0' Centerline North/South road."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found pole barn spike, one(1) of Hunt's accessories and two(2) of Mitchell's accessories. Distances to adjacent corners were reasonable consistent. Accepted spike as the best evidence of the original GLO post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD SEPTEMBER 25, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced spike with Harrison Marker on 12/19/96.

- N 73°E 45.5' Stop/Street Sign Post
- WSW 51.4' Stop Sign Post
- S37°W 86.01' Nail & Tag in Power Pole
- West 5' Centerline 52nd Street



Signed by Gary C. Bilow
Surveyor's Michigan License No. 26453

Date December 19, 1996