

FILED

MAY 16 1997

DEC 10 8 24 AM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Arlington Township

| | | |
|---|--------------------------|---------------|
| Van Buren County <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey S 1/4 Post Sec 10 | T <u>2S</u> R <u>15W</u> | <u>H-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

9-00
12709 0101 10SURVEY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | |
| 3 | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | |
| 5 | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | |
| 7 | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | |
| 9 | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | |
| 11 | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | |
| 13 | | | | | | | | | | |

I, Donald R. Gilchrist, in a field survey on October 31, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
8/30/1830 - GOVERNMENT - George W. Harrison, D.S.
 Ran East - Intersected E boundary at 207 lks N of post - 79.70 chs - Corrected and set 1/4 Post at 39.85 chs.
11/7 to 18/1900 - George Mutchler, C.S.
 Found Stone. 9" Sugar - S 11 Deg 45' E - 39.5 lks. 8" Sugar S 38 Deg 30' W - 49.25 lks.
 Meas W 1315.71' to Iron at 1/8 Pt & 1315.71' to Sec Cor of Stake & Brick.
 Meas East 1314.72' to 1/8 Pt & 1314.72' to Sec Cor Stone - 2629.44'.
 Meas North 1315.71' to 1/8 Pt, Iron & 1315.71' to Cen 1/4 Pt, Well Point.
 (Continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
8/96 Found 1/2" Iron in Mon Box - Raised Mon Box - Set Harrison Marker over 1/2" Iron in Mon Box.

Approved at the 2/24/93 Meeting of the Van Buren County Peer Group and is accepted as the best available evidence of the position of the original corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date 12/9/96 D. R. G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Harrison Marker in Mon Box.
 4" Will - N 44 Deg E - 156.78'.
 34" Spruce - N 43 Deg W - 125.97'.
 22" Ch Elm - S 54 Deg W - 79.74'.
 "X" in top of R/W Marker - S - 60.00'.
 0.60' N of CL M-43.



Signed by Donald R. Gilchrist
Surveyor's Michigan License No. RLS 13583

Date 12/2/96

1949 - M.S.H.D.

Shows Cor 0.60' N of CL of M-43 Hwy.

12/2/77 - Gove Associates - W. Q. Smith

Survey of SE 1/4 of Sec (Recorded Liber 8-Page 75).

1/23/78 - W. Q. Smith. C.S.

Rec'd Corner. Found empty Mon Box from wit's. Set Iron in Center.

R/W Marker - S - 60.0' to CL. R/W Marker - N - 59.1' to CL.

10/1995 - D. R. Gilchrist, C.S.

Tied Cor off for reconstruction of M-43. Fd 1/2" Iron Mon Box.

LIBER 4 PAGE 378