

Van Buren County Remonumentation Program Dec 20 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Center of Section 22

For corners in Arlington Township

Mark A. Smith  
VAN BUREN CO.  
REGISTERED SURVEYOR

7-00  
12/20 0101 10SURVEY  
41

Van Buren (County)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 15W	H8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Liber 4 PAGE 483

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on 5/28, 19 93 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
Post not established by original government survey. Found no records of corner ever being established.

SURVEY &  
REMONUMENTATION  
MAY 16 1997  
COMMISSION

Ratified by Peer Group in  
accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date 12/20/96 D. H. G.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1-1/2" Well Point at the intersection of old downed fences projecting 1.5' above ground. Well Point is 2' North and 5' East of the calculated 1/4 line intersection. Accepted Well Point as the corner.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTAION PEER GROUP OF SURVEYORS AT A MEETING HELD OCTOBER 9, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced Well Point with Harrison Monument on 12/19/96

S73°E	6.64'	Nail & Tag in 10" Maple
S2°W	25.89'	Nail & Tag in 8" Maple
N66°W	29.34'	Nail & Tag in 8" Beech
N15°W	31.99'	Nail & Tag in 15" Beech



Signed by Gary C. Bilow  
Surveyor's Michigan License No. 26453

Date December 19, 1996