

MAY 16 1997

Van Buren County Remonumentation Program Dec 20 2 47 PM '96

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Quarter Corner 22,27

For corners in Arlington Township

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

7-00

Van Buren
(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 15W H9
T R
T R
T R

2. Property Controlling
in Section

S T R Ratified by Peer Group in
S T R accordance with P.A. 345 of 1990
S T R Van Buren County Surveyor

3. Miscellaneous
Property in Sec.

S T R
Date 12/20/96 *D. P. A.*

Like 4 Page 487

Register of Deeds Stamp & File Number

12/20 0101 10SURVEY
411

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary C. Bilow, in a field survey on 5/28, 19 93 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories - Beech 22 S17E 21 links and Lynn (Basswood) 10 N33E 23 links. County Surveyor A.J. Pierce in 1869 recorded in Volume 3 Page 78 "Stake gone - accessories: 16" Lynn East 73." George Mitchell (PS #19618) reports on an unrecorded survey "Found 1" Iron pipe - accessories - SW 47.55' scaffold nail in 16" Ash, SE 49.00' 8" Ash, NNE 28.6' 10" Poplar, and South 4.0' centerline East-West road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 1" Iron Pipe and three (3) of Mitchell's accessories. Distances to adjacent corners were reasonable and consistent. Accepted 1" Iron pipe as the best evidence of the original post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD SEPTEMBER 25, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Replaced 1" Iron Pipe with Harrison Monument on 12/19/96

S48°W	47.51'	Scaffold nail in 16" Ash
N16°E	28.0'	Face of 11" Poplar
South	4.0'	Centerline of 40th Avenue
N20W	29.23'	Nail & Tag in Power Pole



Signed by *Gary C. Bilow*
Surveyor's Michigan License No. 26453

Date December 19, 1996