

MAY 16 1997 Van Buren County Remonumentation Program 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Section Corner 14,15,22,23

COMMISSION For corners in Arlington Township

Mark A. Smith VAN BUREN CO. REGISTER OF DEEDS

7.00

| Van Buren (County)                 | Located in: | Corner Code #  |
|------------------------------------|-------------|--|
| 1. Public Land Survey              | T 2S R 15W  | 17   |
|                                    | T R         |  |
|                                    | T R         |  |
|                                    | T R         |  |
| 2. Property Controlling in Section | S T R       | Relieved by Peer Group in accordance with P.A. 345 of 1990 |
| 3. Miscellaneous Property in Sec.  | S T R       | Van Buren County Surveyor                                  |

Liber 4 Page 485

Register of Deeds Stamp & File Number

12/20 0101 10SURVEY 412

4. Lot No. Recorded Plat 5. Private Claims

I, Gary C. Bilow, in a field survey on 5/28, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:  
 Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories: Sugar 20 S29E 6 links and Beech 18 S56W 7 links. County Surveyor W.H. Goss recorded in 1907 in the Red Book Page 23 "Stone - accessories: 10" Walnut SW 77 links." County Surveyor T.A. Smith recorded in 1927 in his field notes "Stone found-accessories: 12" Elm N43W 43.8' to center, 15" Elm S76E 22.9' to center, 18" Maple N15E 75.9' to center, and 18" Walnut S35W 51.2' to center." E. Stefan (PS #13599) recorded on a Act 132 Survey recorded in Liber 1 Page 268 "Iron-accessories: West 21.0' edge Street Sign, N35W 39.62' Nail in 10" tree, and N45E 44.6' edge Stop Sign." Alton Howard (PS #2382) in an Act 132 Survey recorded in Liber 2 Page 255 "Iron pipe-accessories: N45E 206.2' Telephone pole and West 21.5' Street sign."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1/4" x 1" Iron Bar over large stone and two (2) of Stefan's accessories. Distances to adjacent corners were reasonable and consistent. Accepted this Iron Bar as the best evidence of the original GLO post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD OCTOBER 9, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced 1/4" x 1" Iron Bar and stone with Harrison Monument on 12/18/96

|       |        |                        |
|-------|--------|------------------------|
| West  | 21.0'  | Street sign post       |
| N45°W | 39.35' | Nail in 10" dead Ash   |
| S52°W | 32.56' | Nail in 13" Ash        |
| East  | 1'     | centerline 50th Street |
| North | 3'     | centerline 36th Avenue |
| N35°E | 66.59' | nail in 16" Maple      |



Signed by Gary C. Bilow 26453 Surveyor's Michigan License No.

Date December 19, 1996