

FILED

SURVEY & REMONUMENTATION

MAY 18 1997

Van Buren County Remonumentation Program DEC 20 2 47 PM '96

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Quarter Corner 22,23

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

7-00

For corners in Arlington Township

Van Buren
(County)

Located in:

Corner Code #

1. Public Land Survey

T2S R15W 18

2. Property Controlling in Section

S T R Ballied by Peer Group in
S T R accordance with P.A. 345 of 1990
S T R Van Buren County Surveyor

3. Miscellaneous Property in Sec.

S T R
Date 12/20/96 D. R. G.

4. Lot No. Recorded Plat

5. Private Claims

Liber 4 Page 486
Register of Deeds Stamp & File Number

12/20 0101 10SURVEY

I, Gary C. Bilow, in a field survey on 5/28, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
Post established by U.S. Deputy Surveyor G. Harrison in 1830 - accessories: Sugar 13 N37W 4 links and Sugar 13 N54E 9 links. E. Stefan (PS #13599) recorded on a Act 132 Survey recorded in 1972 in Liber 1 Page 268 "RR spike - accessories: N70W 26.2' Iron pipe, S45E 50.6' Face 30" tree stump, N18E 98.73' Face of Telephone Pole, and Fence on line West."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found RR spike and two (2) of Stefan's accessories. Distances to adjacent corners were reasonable and consistent. Accepted RR spike as the best evidence of the original GLO post.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD OCTOBER 9, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced RR spike with Harrison Monument on 12/19/96

- N73°W 26.1' Iron pipe
- S35°E 50.6' Face 30" tree stump
- West 33.00' DNR monument
- East 2.0' centerline 50th Street
- North 6.0' centerline 38th Avenue



Signed by Gary C. Bilow
Surveyor's Michigan License No. 26453

Date December 19, 1996