

NOV 15 1994

FILED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

OCT 18 12 03 PM '94

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 160

For corners in Arlington Township

Van Buren County (County)

Located In:

Corner Code #

Mark A. Smith
VAN BUREN CO
REGISTERED DEEDS

7.00

- 1. Public Land Survey SE Cor Sec 35. T 2 S R 15 W K-13
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Register of Deeds Stamp & File Number

10/18 0101 105URVEY

I, Donald R. Gilchrist, in a field survey on September 26, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Feb 8, 1830 - G.W. Harrison, D.S., 80.00 ch to Sec Corn 35 & 36 on a Tamarac 11". Sept 11, 1867 - C.D. Lawton, Co.Surveyor (B1-46) - NE cor Sec 2, T3S, R15W, Lawrence Twp., found stake & both wit's trees, set new stake. May 9, 1868 - A.J. Pierce, Dep.Co.Surveyor (B3-77) - use above Lawrence corner, ? he jog 1.30 ch E to Lawrence corner. Aug 27, 1973 - W.Q. Smith & D. Gilchrist, Co.Surveyor - found corner & found 1/4 post, set Lawrence Twp 1/4 post at 85.81' jog (Rec'd B2-229). 1981 - J.C. Hunt - found iron bolt.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron bar. Removed and set standard cast iron monument (rec'd L3, P265)

Corner was field checked on 9/26/94 by D.R. Gilchrist, Co.Surveyor. Approved at the 10/5/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

Ratified by Peer Group in accordance with P.A. 345 of 1998 Van Buren County Surveyor

Date D. R. G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard monument - Harrison Marker
Nail in 12" walnut N 45° W 78.58'
Top C/L Tele Pedestal S 30° W 44.98'
Top C/L Tele Pedestal S 20° E 39.05'
6' ± E of CL Rd N
1' ± N of CL E & W Rd

Signed by Donald R. Gilchrist Date 10/3/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

