

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

CORNER COMMON TO SEC. 3, 4, 9, & 10

For corners in BANGOR TWP.

VAN BUREN
(County)

Located In:

Corner Code #

1. Public Land Survey Sec. 10 T2 S. R 16 W. G-3
 T R
 T R
 T R
2. Property Controlling S T R
 in Section S T R
3. Miscellaneous S T R
 Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
 Oct 8 9 09 AM '96
 Mark A. Smith
 VAN BUREN CO.
 REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S. in a field survey on September 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration: G-3
 4/1830 Gov. GW Harrison DS; wit. 13" beech N62°E 4 lks. (2.64') & 6" sugar maple N72°W 4 lks.
 1/1868 AJ Pierce DCS surveys in Bk. 3 pgs. 4 & 62. 11/1883 AA Fosdick CS Fd. witness tree & old stake. Set stone in place. 10/1893 G Mutchler CS: Fd. stone & roots of one witness tree. Distance N. is 2640' to quarter post. 1900+- WH Goss CS: Fd. stone, wit.: 8" hickory N5°E 66 lks. (43.56'). 1966 WQ Smith CS, C.P. Co., DR Gilchrist, field: Fd. stone. Distance N. is 1326.90' to 1/8th post & continued N. 1326.90' to W 1/4 post for total of 2653.80'. Distance E. of 1330.21' to 1/8th post & continued E. 1330.21' to S 1/4 post for total of 2660.42'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-3 NW corner Sec. 10, T2S-R16W, Bangor Twp. (Corner common to Sections 3, 4, 9, & 10.)
 Found wood stake on E. side of stone with nail & cap in top. Set Harrison Marker with Survey Marker Sign Post. N89°40'30"E 2660.36' to N 1/4 post of Sec. 10.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 26, 1996, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Restored by Peer Group in accordance with P.A. 345 of 1998
 Van Buren County Surveyor

Date 10/8/1996 J. R. G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-3 HARRISON MARKER

N04°E 42.48', nail & tag in SW root of 22" hickory
 N75°W 40.53' nail & tag in N. face of 10" maple
 N47°W 26.09', nail & tag in SW face of 12" tree
 N57°E 46.90', nail & tag in S. base of 10" hickory

SURVEY & REMONUMENTATION

MAY 16 1997

COMMISSION

Signed by John C. Hunt, P.S.
 Surveyor's Michigan License No. 23513

Date Sept. 12, 1996

