

DEC 2 2 54 PM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bangor Township

Van Buren County
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 16W 9H
S~~X~~ Post Section 22 T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Mark A. Smith
REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

I, Donald R. Gilchrist in a field survey on 11/22/93, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4/1830 - GOVERNMENT SURVEY - George W. Harrison D.S.
Set 1/4 Section Post at 39.92 ch. (2634.72').
4/30/1884 - A.A. Fosdick, C.S.
Book 5 Page 28
Ran 1/4 lines to set Center 1/4 Post of Section 22
Found All Corners
Witnesses: 3" Butternut - S 89 Deg 30' East - 84 lks. (55.44')
12" Sugar - S 18 Deg 30' West - 97 lks. (64.02')
(A is continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe (bent) and brass cap gone
Checked Fosdick and T.A. Smith Witnesses
Maple - S 18 Deg 30' West - 64.02' - T.A. 64.4'
Set Harrison Marker where pipe went straight

Approved at 7/14/93 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker
16" W.Cherry - West - 27.03' to Pk/W in North side
42" Maple - S 18 Deg 30' West - 64.36' to Pk/W in East side
24" Maple - N 22 Deg 30' West - 55.00' to Pk/W in East side
28" W.Cherry - S 55 Deg East - 35.22' to Pk/W in Southwest side
Steel corner fence post - East - 29.10' to face
4'± East to centerline of road



Signed by Donald R. Gilchrist Date 11/22/93
Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

LIBER 4 PAGE 88

A. Continued from front of Certificate

7/17/1936 - T.A. Smith, C.S.

Red Book and Field Notes

Could not find the Stone here, found 1 witness tree

Sugar witness is OK

Found butternut stump

Drove pipe in line with fence East & West

Witnesses: 30" Maple - S 15 Deg West - 56.6' to center line

Steel Fence Post - E 19.5' on fence North

Steel Fence Post - E 25.8' on fence South

1940± - Old field note

Shows corner

1950± - Additions to field notes

Measured Center 1/4 Post to North 1/4 Post, Section 27 = 2629.0'

On back of field note

Found stone and glass bottle. Placed pipe with brass cap over stone

Witnesses: spike in West side 36" Maple - S 20 Deg West - 64.4'

spike in West side 14" Cherry - 55 Deg East - 34.1'

spike in West side 8" Maple - N 22 Deg 30' West -

56.15'

in line with fence East and West

1/19/1976 - George Mitchell, P.S.

Found State brass cap

Recordation certificate (L2-P445 See Sheet)