

SEP 18 1997

MAR 27 8 42 AM '97

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

N.W. COR., SEC. 5

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Antwerp Township

Van Buren (County)

Located In:

Corner Code #

Mark A. Smith
VAN BUREN CO REGISTER OF DEEDS

- 1. Public Land Survey T 3S R 13W C-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Liber 4 page 492

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Allen H. McMachen, in a field survey on February 13, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829 - William Brookfield, D.S., Intersected North boundary 213 lks. (140.58') East of post. Set post at intersection, 10" Bl. Oak S. 32° 30' W. 24 lks., 14" Bl. Oak S. 04° 30' E. 77 lks.

1971 - A.H. McMachen, R.L.S., Found railroad spike, set iron rod in mon box, 36" Oak N. 40° W. 85.57', 15" Oak, S. 75° W. 60.94', 36" Oak S. 15° E. 55.61', Bolt in centerline West 7.81', centerline road East & West is North 16'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box matching (4) 1971 witnesses, 36" Oak now being only a stump, said iron rod also being ±140.7' (gov't. = 140.58') East of found iron bar at Southwest corner, Section 32, Almena Twp., Removed iron rod and box, excavated to depth of 4' finding no additional evidence of corner. Location of iron rod was ratified by the Van Buren County Remonumentation Peer Group on January 29, 1997.

THIS TRANSFER MADE BY
MARK A. SMITH
REGISTER OF DEEDS
VAN BUREN COUNTY

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 3/27/97 D. P. G.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The location of found iron rod is accepted as the best available evidence of the position of the original corner. Replaced iron rod with a standard Van Buren County Remonumentation monument with monument box over, Accessories:

- "PK" Nail in West side of 42" Maple S. 10° E. 146.84'
- "PK" Nail in South side of 40" Oak S. 80° W. 154.42'
- "PK" Nail in Southwesterly side of 40" Oak N. 70° W. 132.61'
- "PK" Nail in Northeasterly side of 40" Oak N. 30° W. 86.06'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 2/24/97