

JAN 17 1996

DEC 22 9 52 AM '95

LAND CORNER RECORDATION CERTIFICATE  
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS

Van Buren  
(County)  
Antwerp Twp.

Located In: S.W. Cor. Sec. 15 Corner Code # G-7

1. Public Land Survey	T <u>3</u> S R <u>13</u> W	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, James E. Boynton, in a field survey on October 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829, original corner established by William Brookfield, D.S.  
 1891, G. Muchler, C.S. used corner - no description given  
 1920, stone found and witnessed by Homer Ward, Road Engineer  
 1972, R.R. Spike found and used by D.R. Gilchrist  
 1974, 1975, 1977, 1978 and 1994 - R.R. Spike found & used

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. Spike over stone over bricks from 1974 witnesses. Set standard marker in position as best evidence of original corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
 Van Buren County Surveyor


Date 9-6-95 D.R.A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard marker as directed by Peer Group on September 6, 1995.

24" Walnut N. 20° E. 105.31'  
 36" Maple S. 18° E. 89.04'  
 24" Oak S. 30° W. 74.40'

N.E. corner of brick house N. 40° W.



Signed by James E. Boynton Date 12-17-95

Surveyor's Michigan License No. 29239

*Liber 4 Pg. 340*