

Dec 20 1 43 PM '99

7-00

8890 12/20 0104 10SURVEY

W 1/4 cor., Sec. 34

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ANTWERP TWP.
VAN BUREN

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S.</u> R <u>13W.</u>	<u>G-12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on December 8, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1829 - William Brookfield, D.S., Set quarter Section post, 7" Hickory S. 47° 30' W. 9 lks. (5.94'), 8" Hickory S. 71° E. 37 lks. (24.42')
- 1900± - W.H. Goss, C.S., Square stone, 12" Sugar S. 31° W. 57 lks. (37.62'), 25" Sugar S. 84° E. 48 lks. (31.68')
- 1923 - T.A. Smith, C.S., Found square stone standing on end - top 6" below grade, 12" Walnut N. 35° W. 38.6' to centerline, 12" Maple N. 10° W. 100.00' to centerline, 30" Maple S. 85° E. 32.6' to centerline, 12" Apple S. 65° E. 59.5' to centerline, 24" Maple S. 45° E. 45.3' to centerline, 24" Maple S. 40° W. 38.6' to centerline.
- 1922 - W.Q. Smith, C.S., Found pipe and 60 penny over, 36" Maple S. 85° E. 32.6' to centerline, 30" Maple S. 45° E. 45.3' to centerline, 30" Maple S. 40° W. 38.6' to centerline.
- 1995 - J.C. Hunt, P.S., East 31.07' - Mag nail North root of 38" Maple, S. 44° E. 46.17', Mag Nail Southwest root 34" Maple, S. 25° W. 35.90' - Mag nail East root 38" Maple, S. 70° W. 47.04' - Mag nail North face 3" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 60d nail in pipe per (2) 1995 witnesses 0.5' below grade. Removed pipe (2' long) and found square stone standing on end. Pipe ran down South side of stone with top of pipe being 0.1' South and 0.06' West of stone. Found square stone was ratified by the Van Buren County Remonumentation Peer Group on November 27, 1999.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date 12-20-99 *D. B. A.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found square stone is accepted as a careful and faithful perpetuation of the position of the original corner. Replaced square stone with a Standard Van Buren County Remonumentation Monument with monument box over, Accessories:

- Nail & Tab in East root of 36" Oak N. 05° W. 132.81'
- Nail & Tab in North side of 30" Oak S. 78° E. 31.63'
- Nail & Tab in SW root of 30" Oak S. 40° E. 46.19'
- Nail & Tab in East root of 36" Oak S. 33° W. 36.00'
- 3' West of centerline North and South road



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 12/14/99

L. Lee 5 Pg. 303