

MAY 16 1997

FILED

COMMISSION
N. 1/4 COR. SEC. 35

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 18 9 36 AM '96

For corners in Antwerp Township
Van Buren
(County)

Located In: Corner Code #

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

1. Public Land Survey	T	3S.	R	13W.	J-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

LIBERTY PAGE 465

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 2680

I, Allen H. McMachen, in a field survey on June 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|--|---|
| <u>1829</u> - William Brookfield, D.S.
14" Wh. Oak S. 89° E. 54 lks.
10" Wh. Oak N. 18° 30' E. 63 lks. | <u>1971</u> - A.H. McMachen, R.L.S.
Found stone with "X" on top, 26" Oak, N. 10° E. 2.84'
7" Hickory N. 45° W., 14.41'
Fence corner West 15.8'
6" Oak S. 88° E. 35.76' | <u>1992</u> - G. Mitchell, P.S.
Found pointed stone
"T" Fence post S.W. 0.50'
4" Maple E.S.E. 6.9'
38" Oak East 17.0' (face)
6" Hickory N.N.E. 12.7' (face)
8" Poplar W.S.W. 11.28' |
|--|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone with "X" on top surrounded by smaller stones per 1992 witnesses. Stone was ratified by the Van Buren County Remonumentation Peer Group on March 27, 1996 and is accepted as careful and faithful perpetuation of the original corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date 12/18/96 D. R. L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed stone and replaced with a standard Van Buren County Remonumentation monument, Accessories:

- "PK" Nail in 6" Oak N. 40° E. 21.84'
- "PK" Nail in 38" Oak East 18.13'
- "PK" Nail in 8" Oak West 11.63'
- "PK" Nail in 10" Oak N. 50° W. 21.30'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 10/3/96

399312/18 0101 10SURVEY 7.00