

DEC 18 9 36 AM '96

SE. COR. SEC. 35

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners Antwerp Township  
Van Buren  
(County)

Located In:

Corner Code #

Mark A. Smith  
VAN BUREN CO.  
REGISTER OF DEEDS

7.00  
12/18 0101 10SURVEY

1. Public Land Survey	T	3S.	R	13W.	K-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

LIBER 4 PAGE 469  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

6. IWM Job No. 2680  
I, Allen H. McMachen, in a field survey on October 15, 1996  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
  
1829 - William Brookfield, D.S.  
Set Post corner  
30" Wh. Oak N. 31° 15' E. 75 lks.  
14" Wh. Oak N. 64° 30' W. 69 lks.  
  
1971 - A.H. McMachen, R.L.S.  
Set iron rod at 21.12' (Gov. Jog) East of the NE corner, Section 2, Porter Township  
30" Maple S. 50° W. 67.98', T.P. N. 60° W. 37.15'  
Corner grapes N. 45° E. 35.71'  
2' East of centerline, 1/4" pipe West 21.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
  
Found iron rod per 1971 witnesses. Removed iron and excavated below. Found 1' X 2' stone sitting on end surrounded by red brick. Stone was ratified by the Van Buren County Remonumentation Peer Group on May 1, 1996 and accepted as the best available evidence of the position of the corner.

SURVEY &  
REMONUMENTATION  
  
MAY 1 6 1997  
  
COMMISSION

Ratified by Peer Group in  
accordance with P.A. 345 of 1990  
Van Buren County Surveyor  
Date 12/18/96 J.P.A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
  
Replaced found stone with a standard Van Buren County Remonumentation monument and mon. box over,  
Accessories:  
  
"PK" Nail in 10" Maple S. 75° E. 88.19'  
"PK" Nail in 36" Maple S. 30° W. 107.80'  
"PK" Nail in 36" Maple S. 55° W. 68.02'  
"PK" Nail in 36" Maple S. 75° W. 119.19'



Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 10/25/96