

1993 VAN BUREN COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Van Buren (County) Located In: Antwerp Twp. Corner Code #/ M-8

1. Public Land Survey Sec. 24 T 3 S. R 13 W.
T. R.
T. R.
T. R.

2. Property Controlling S. T. R.
in Section S. T. R.

3. Miscellaneous S. T. R.
Property in Sec. S. T. R.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Hunt, in a field survey on February 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Apr. 1829 Wm. Brookfield, D.S. set corner. Witnesses: 13" Poplar S.18°W. 18 lks.; 14" Maple N.59½°W. 9 lks.; Jog: 1,735 Ch = 114.51'. In 1930 T.A. Smith, C.S. fd. stone, set iron over it. Wit. OK: 30" Maple S.40+°E. 48'; 24" Maple S.85+°E. 29.1'. 12/14/75 I.W.M. set ½" I.R. 114.51' S. of W½ post Sec. 19 Texas Twp. on W. line of Sec. 19 projected S. J. Hunt fd. iron 114.7' S. of mon box for Kal. Co. in 1980, 1981, 1984, & 1987. 8/11/89 Gove Assoc. fd. iron. 9/3/90 D. Gilchrist, C.S. fd. 1" pipe, set iron bar over, witnessed on survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2/3/93 J. Hunt fd. ½" I.R. in mon box in C/L of road. Removed ½" I.R. & set Harrison Marker as per instructions of Remonumentation Committee Peer Group at meeting held on Jan. 27, 1993.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 Harrison Marker in mon box.
North 114.44', ½" I.R. in mon box.
West 50' & 100', ½" I.R. 3' N. of fence; irons in line w/ cor.
S.86°W. 35.25' Nail N.E. cor. R.R. tie post.
S.27°40'W. 82.00' Nail N.W. face pole.
N.16°20'W. 126.25' Nail & washer South face pole.
1.2' South & 1.1' East of cor., ½" I.R.

Signed by John C. Hunt Date Feb. 10, 1993
Surveyor's Michigan License No. 23513