

FILED

Dec 20 1 44 PM '99

7.00

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mark A. Smith
VAN BUREN COUNTY
REGISTER OF DEEDS

BB90 12/20 0104 105URVEY

W 1/4 cor., Sec. 9

For corners in PAW PAW TWP.
VAN BUREN
(County)

Located In: Corner Code #

1. Public Land Survey	T 3S. R 14W.	E 4
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY & REGISTER OF DEEDS

DEC 28 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on November 17 1999 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - William Brookfield, D.S., Set quarter Section post, 12" Wh. Oak N. 89° E. 53 lks. (34.98'), 16" Wh. Oak N. 2° E. 42 lks. (27.72')
- 1924 - T.A. Smith, C.S., "Found large stone 1" above surface of roadway nearly in line with Wildey Cemetery fence - drove 3/4" pipe 6" South of stone, 30" Oak East 62.5 feet to center line; near corner of James Wilson's slab marker - 49.8'; near corner of stone for children of J.H. and R.H. Prater - 59.6'.
- 1972 - A.H. McMachen, R.L.S., "Found iron pipe" - matching 2 of the 1924 witnesses.
- 5/1988 - D.R. Gilchrist, C.S., Found 5/8" pipe, 36" Oak S. 30° W. 17.64', North corner James Wilson headstone S. 80° E. 50.30', center line South post in sign N. 15° W. 29.23', 7' West of center line of North and South road; 30 feet South of center line to East.
- 8/1988 - D.R. Gilchrist, C.S., Set mon. box over 3/4" pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in mon. box per (3) 1988 witnesses. Location of found 3/4" pipe was ratified by the Van Buren County Remonumentation Peer Group on April 28, 1999.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date 12-20-99 D. R. L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Location of found 3/4" pipe is accepted as the best available evidence of the position of the original corner. Drove found pipe down 3 feet and placed a Standard Van Buren County Remonumentation Monument over pipe in monument box, Accessories:

- Nail & Tab in South side of 16" Pine S. 75° E. 82.83'
- Nail & Tab in East side of 36" Oak S. 20° W. 41.13'
- Nail & Tab in East side of 40" Oak S. 40° W. 17.05'
- Placed iron rod N. 30° W. 26.65'
- 7' West of center line North and South road
- 30' South of center line road to East



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/13/99

See pg 307