

FILED

Dec 20 1 44 PM '99

7-00

SW cor., Sec. 9

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in PAW PAW TWP.
VAN BUREN
(County)

Located In: Corner Code #

- 1. Public Land Survey T 3S. R 14W. E-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

SURVEY & RECORDED

DEC 28 1999

SECTION

Register of Deeds Stamp & File Number

12/20 0104 10SURVEY

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on November 17/19 99 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - William Brookfield, D.S., Set post corner, 16" Wh. Oak S. 65° 15' E. 11 lks. (7.26'), 14" Wh. Oak N. 8° E. 44 lks. (29.04')
- 1950± - W.Q. Smith, C.S., Angle South to East is 88° 29' 30".
- 1953± - T.A. Smith, R.L.S., Angle South to East is 88° 28'.
- 1970± - D.R. Gilchrist, R.L.S., Found well point - 2 map witnesses good, angle South to East is 88° 29' 45".
- 1971± - A.H. McMachen, R.L.S., Found 1 1/4" pipe
- 1972 - A.H. McMachen, R.L.S., Found well point, 24" Maple N. 5° W. 90.5', 24" Maple N. 75° W. 85.1'
- 1996 - D.R. Gilchrist, C.S., Found iron bar, cable riser S. 40° W. 33.85', Cable riser S. 45° E. 62.75', 1.5' South of centerline of 56th Ave., 8' West of centerline of 42nd St.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod per (2) 1996 witnesses. Removed iron rod and dug to depth of 3' finding no additional evidence of corner. Found iron rod was ratified by the Van Buren County Remonumentation Peer Group on April 28, 1999.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Location of found iron is accepted as the best available evidence of the position of the original corner. Replaced iron rod with a Standard Van Buren County Remonumentation Monument with monument box over, Accessories:

- Nail & Tab in North side of 40" Maple S. 80° W. 107.61'
- Nail & Tab in East side of 30" Maple S. 10° W. 131.03'
- Placed iron rod N. 23° W. 33.41'
- Placed iron rod N. 30° E. 46.76'
- Placed iron rod S. 40° E. 38.48'
- Placed iron rod S. 40° W. 24.32'
- 1.5' South of East and West road
- 8' West of North and South road

Ratified by Peer Group in accordance with P.A. 345 of 1996
Van Buren County Surveyor

Date 12-20-99 D.R.G.



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/13/99

Rev 5 pg 304