

NOV 15 1994

FILED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 18 12 03 PM '94

LIBER 4 PAGE 176

For corners in Paw Paw Township

Van Buren County
(County)

Located in:

Corner Code #

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

7-00

- 1. Public Land Survey 3S R14W E-10
E 1/4 Post Sec 29
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling _____
in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous _____
Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

7361 10/18 0101 10SURVEY

	A	B	C	D	E	F	G	H	I	J	K	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Donald R. Gilchrist, in a field survey on June 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Jan. 1830 - Government - William Brookfield, D.S., set post at 40 ch.; 10" poplar - N 6 1/2° W - 17 lks.; 9" Poplar - S 86 1/2° E - 10 lks. June 1873 - A.J. Teed, Co. Surveyor, found remains of old stake present, Book 4, P 125; put in new stake & stone on top; 9" B.Oak S 20° E 41 lks. 7/21/1891 - F.P. Lawton, Found stone, Book 5, P 47. April 1953 - W.Q. Smith, Co.Surveyor, shows Iron Pipe on drawing. August 1957 - W.Q. Smith, Co.Surveyor, R.R. spike; 40" Oak - S 29.6'; 12" Hick - N 31'; 48" Oak - SE 46.6'. March 2, 1970, Don Gilchrist, found R.R. spike - used in 8/77-7/76. June 28, 1972 - W.Q. Smith, Co.Surveyor, R.R. Spike (Rec'd Liber 1, P480). John Hunt, found as Rec'd in 1975, 1986 & 1992.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd R.R. Spike 2" under new paving. Two wit's from (rec'd L-1, P480) remain & OK. Third wit's was cut down. Fd another R.R. spike down 6". Set a P.K. 1' S. Set a P.K. 1' W. Set a Harrison Marker. Corner approved at Peer Group Meeting on November 25, 1992. Recorded Liber 3, Pages 260 & 261. Corner was field checked on 6/22/94 by D.R. Gilchrist, Co.Surveyor. Approved at the 6/29/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date D. R. G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

█ Harrison Marker
50" W. Oak - South - 29.41' - Old Nail E side
32" Hick - North - 30.79' - use Old Nail in E side
24" W.Ch. - S 65° E - 82.02' Nail SW side
CL of Rd.



Signed by Donald R. Gilchrist

Date 9/22/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583