

Dec 20 1 44 PM '99

7-00

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

3/4 cor., Sec. 9

For corners in PAW PAW TWP.

VAN BUREN

Located In:

Corner Code #

(County)

- 1. Public Land Survey T 3S. R 14W. F-5
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

SURVEY &

DEC 28 1999

SECTION

Register of Deeds Stamp & File Number

8890 12/20 0104 10SURVEY

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on December 1, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - William Brookfield, D.S., Set quarter Section post
- 1949 - T.A. Smith, C.S., Pipe, Southwest corner of house foundation S. 75° E. 90.75', Northwest corner of house foundation N. 75° E. 93.45', 48" Oak S. 45° W. 43.0'
- 1966± - D.R. Gilchrist, R.L.S., Found pipe
- 1971 - W.Q. Smith, C.S., Found pipe, Northwest corner house foundation - Northeast - 93.45', Southwest corner house foundation - Southeast - 90.75', 24" Maple N. 75° E. 41.33' to nail in South side, Utility pole N. 40° W. 56.64' to nail in North side, Utility pole S. 20° E. 70.44' to nail in Southwest side, Pipe is 5.0 feet West of centerline of North and South road, Pipe is in line with centerline of road to West.
- 1988 - D.R. Gilchrist, C.S., 3/4" pipe and witnesses same as in 1971.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 5 feet West of center line North and South road and in center line road to West. Removed iron (0.5' long) and found 3/4" pipe directly under iron. Removed pipe (2' long) and excavated to a depth of 3 feet, probing an additional 1.5 feet and found no further evidence of corner. Location of found pipe was ratified by the Van Buren County Remonumentation Peer Group on April 28, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Location of the found 3/4" pipe is accepted as the best available evidence of the position of the original corner. Placed a Standard Van Buren County Remonumentation Monument at location of pipe with monument box over, Accessories:

- Nail & Tab in S.W. side U. Pole N. 40° W. 58.05'
- Nail & Tab in S.E. side U. Pole S. 40° W. 57.98'
- Nail & Tab in South side 12" Maple S. 55° E. 45.21'
- Nail & Tab in South side 24" Maple N. 45° E. 56.25'

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12-20-99 D. R. G.



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/14/99

L. Mc 5 pg 3/2