

SURVEY & REMONUMENTATION

JUN 14 1994

VAN BUREN COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Van Buren</u> <small>(County)</small>	Located in: <u>Paw Paw Twp.</u>	Corner Code <u>I-7</u>
1. Public Land Survey	Sec. 14, T <u>3</u> S. R <u>14</u> W. SW corner T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Hunt, P.S. in a field survey on March 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5/1830 W Brookfield DS set post corner & Wit.: 10" White Oak S28°15'W 12.54'; 8" White Oak S44°30'E 15.84'. 4/5/1867 CD Lawton CS, Bk. 2 p.27, Reset E_{1/2} post Sec. 22. Drain notes: Three Mile Lk. & Jennings. Goss, red bk., shows meas. W. on Sec. 22 39.73 chs. (2622.51') to 1/4 post. Wit.: 7" Black Walnut S49°45'W 59.40', 8" Cherry S85°30'W 43.23', Hickory N26°45'W 577.', Walnut N23°45'E 330.0'. 1930 & 40 TA Smith CS, notes & drawing show cor. 12/1958 MDOF shows cor. 5/18/1972 WQ Smith CS by D. Middleton RLS, Rec. Cert. L.1 p.440: Stone; rec. surveys L1 p315, L1 p317, L3 p107, L1 p73; large survey drawing: meas. W 2621.18', meas. E. 2658.62', meas. S. 2658.46', meas. N. to 1/8 post 1331.62'. 10/1974 MDOF Rec. Cert. L2 p257. 9/25/1974 W&W rec. surveys L5 p162, L5 p163.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Southwest corner of Sec. 14, T3S-R14W Paw Paw Township

Found pointed stone with "X" on top and iron rods slanted over. Removed stone and set Harrison Marker with sign post on South side.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Register's Office
Van Buren Co., Mich.

Filed 4-11 1994 8:59 o'clock AM
Recorded
Mark A. Smith/csm Register

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 HARRISON MARKER

S87°E, 28.93', Found MSHD nail & washer in North face 13" Walnut.
S52°30'E, 25.03', Set nail & tag in North face of 20" Walnut.
S10°E, 90.72', Set nail & tag in West face 17" Walnut.
N0°30'E, 58.05', Set nail & tag in East face 18" Hickory.

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

6/9/94 DR Reich

LIBER 4 PAGE 136

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date _____

Signed by John C. Hunt, P.S. Date March 10, 1994
Surveyor's Michigan License No. 23513