

#96-17292 f  
K7R3-14.tff

MAY 16 1997 VAN BUREN COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 17 2 24 PM '96

For corners in PAW PAW TWP.

Van Buren (County)	Located In:	Corner Code #
1. Public Land Survey SW corner Sec. 13	T 3 S. R 14 W. T _____ R _____ T _____ R _____ T _____ R _____	K-7 _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Mark A. Smith*  
VAN BUREN CO  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S. in a field survey on November 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

5/11/1830 Gov. W.Brockfield DS: N. bet. sec. 23 & 24 80ch. Set post cor. Wit.: 11" elm N14°30'E 7.26', 10" beech S44°E 13.86'. Dist. W: 5289.90', E 5296.50'. 8/6/1952 T.Smith CS: Sec. 13/14; note shows cor. on N. edge rd. ROW; dist. E to rd. C/L 1775.4'. 2/12/1956 W.Smith CS: Sec. 24 note shows cor. 6/9/1971 LCRC L.1 p.70. MSHD mon. Wit.: in E&W fence 25.5' N. of C/L rd.; 40" ash S75°E 32.15'. 1/19/1972 Dist. N. 2638.36', dist. W. 2652.16'. 9/27/1991 D.Gilchrist CS, Sec. 24 MSHD mon. Wit.: 40" ash S.75°E 32.15', 25.5' N. of C/L 60th Ave. Dist. E to C/L rd. 1783.23', dist. to EX post 2681.90'. 5/22/1995 J.Hunt PS, Sec. 24, Rec. survey L.10 p.184, shows corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Southwest corner Section 13, T3S-R14W, Paw Paw Twp., Van Buren Co., MI. (Corner common to sections 13, 14, 23, & 24.) Corner evidence found: Found 1" iron pipe with M.S.H.D. marker on top. Removed marker & set Harrison Marker (no monument box) in its place with survey marker witness post. Corner is 25.5' North of centerline of road.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON SEPTEMBER 4, 1996, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group in  
accordance with P.A. 345 of 1996  
Van Buren County Surveyor

Date 12/17/96 *D. R. A.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 HARRISON MARKER

N04°W 50.55' Set nail & washer in East face of 10" Ash.  
N19°E 64.79' Set nail & washer in West face of 11" Ash.  
N46°E 75.22' Set nail & washer in West face of 11" Oak.  
N28°W 93.22' Set nail & washer in East face of 20" Ash.



Signed by John C. Hunt, P.S.

Date Dec. 16, 1996

Surveyor's Michigan License No. 23513

*Lib 4 page 449*