

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Dec 16 9 20 AM '99

W 1/4 Post, Sec 24, Paw Paw Twp.

FOR CORNERS OF:	LOCATED IN:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____, T. <u>3</u> S., R. <u>14</u> W.	<u>X</u>	<u>K-8</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ S., R. _____ W.	<u>N.</u>	
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S., R. _____ W.	<u>N.</u>	
4. LOT NO _____, RECORDED PLA _____		
5. PRIVATE CLAIMS _____		

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

DEC 28 1999

SECTION

REGISTER OF DEEDS STAMP
AND FILING NUMBER

I, Charles D. Lossie, in a field survey on 08-Dec, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not More than 2 corners, all in the same town and range may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
5/1830-GOVERNMENT - WILLIAM BROOKFIELD, D.S.

Ran North between Sections 23 and 24 a distance of 40.00 chs. (2640.00') and set Quarter Section Post.

Witnesses:

16" White Oak - N. 30° E., 38 lks. (25.08').

14" Tree S. 65° W., 38 lks (25.08').

See back page for additional history.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found concrete fence post down, re-set Harrison Marker for old Smith & Smith survey for Treatment Plant 1972. The position of this Government Monument was accepted and restored with the approval of the Van Buren County Remonumentation Peer Group of Surveyor's on September 1, 1999 as a careful and faithful re-establishment of the position of the original corners.

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12-16-99 D. R. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison Marker

Iron, N. 18°-58'-19" E., 59.09'

Iron, East, 22.09'

Iron, S. 45° W., 25.87'

Iron, N. 30° W., 27.94'

4" Oak, N. 25° W., 126.59' to Mag Nail 5' ± above ground.

Signed by Charles D. Lossie
CHARLES D. LOSSIE, P.S.



Surveyor's Michigan License No. 44291

L. Ker 5 Pg. 286

West Quarter Post, Section 24, Town 3 South, Range 14 West
Paw Paw Twp., (K-8)

1888 - A. A. FOSDICK, C.S.

Section 23

Book 5 - Page 35

Found Quarter Post - Ran East and West Quarter Line.

Distance West is 39.92 chs. (2634.72').

REF SURVEY & RECORDS

DEC 28 1999

SECTION

5/4/1904 - W.H. GOSS, C.S.

Section 24

Red Book, Book 1 - Page 168

Found Quarter Post.

Found old stake and stump of one Government Witness.

Witnesses:

8" Walnut - N. 89° W., 60 lks. (39.60').

Distance East is 40.57 chs. (2677.62').

4/10/1924 - T.A. SMITH, C.S.

Section 24

Red Book

Distance South is 1321.3' and continuing South 1321.3' to Southwest Corner of Section for a total of 2642.60'.

4/18/1972 - W.Q. SMITH, C.S.

Section 23

Treatment Plant Survey.

Distance South is 1319.18' and continuing South 1319.18' to Southeast Corner of Section for a total of 2638.36'.

Distance North is 1320.40' and continuing North 1320.40' to Northeast Corner of Section for a total of 2640.80'.

Distance West is 1330.61' and continuing West 1330.61' to center Quarter Post for a total of 2661.22'.

Recordation Certificate (Liber 1 - Page 446) by D.A. Middleton, R.L.S. (W.Q.S.).

East Quarter Post is Concrete Fence Post.

Witnesses:

30" Oak - N. 30° E., 73.26' to Tack and Washer.

6" Oak - N. 05° W., 25.18' to Tack and Washer.

14" Elm - West 4.42' to Tack and Washer.

1 1/2" pipe - S. 80° W., 4.35' to Centerline in fence North and South.

9/11/1974 - Recorded Survey (Liber 8 - Page 105).

Section 23

Same as above.

2/26/1988 - D.R. GILCHRIST, C.S. (ALPHA ENG.).

Section 24

Recorded Survey (Liber 9 - Page 166).

Distance East is 2676.68'.

Distance West is 2661.98'.

Distance North is 2640.60'.

Distance South is 2638.78'.

9/26/1991 - D.R. GILCHRIST, C.S.

Section 24

Survey Drawing - Same as above.

2/18/1992 - Survey Drawing - Same as above.

9/14/1993 - Recorded Survey (Liber 10 - Page 26) - Same as above.