

NOV 15 1994

FILED

COMMISSION LIBER 4 PAGE 175

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

OCT 18 12 03 PM '94

For corners in Paw Paw Township

Van Buren County (County)

Located In:

Corner Code: #

Mark A. Smith VAN BUREN CO. REGISTERED PROFESSIONAL SURVEYOR

7-00 10/18 0101 10SURVEY

- 1. Public Land Survey SE Cor, Sec 24 T 3S R14W M-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Donald R. Gilchrist, in a field survey on June 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (2,6) contains '6', (2,5) contains '5', (2,4) contains '4', (2,3) contains '3', (2,2) contains '2', (2,1) contains '1'. Cell (4,7) contains '7', (4,8) contains '8', (4,9) contains '9', (4,10) contains '10', (4,11) contains '11', (4,12) contains '12'. Cell (6,18) contains '18', (6,17) contains '17', (6,16) contains '16', (6,15) contains '15', (6,14) contains '14', (6,13) contains '13'. Cell (8,19) contains '19', (8,20) contains '20', (8,21) contains '21', (8,22) contains '22', (8,23) contains '23', (8,24) contains '24'. Cell (10,30) contains '30', (10,29) contains '29', (10,28) contains '28', (10,27) contains '27', (10,26) contains '26', (10,25) contains '25'. Cell (12,31) contains '31', (12,32) contains '32', (12,33) contains '33', (12,34) contains '34', (12,35) contains '35', (12,36) contains '36'. Cell (13,13) contains '7361'.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Government set post corner - 6" White Oak - S 32°30' W - 53 lks. 9" White Oak - N 33°30' W - 28 lks. W.H. Goss, Co.Surveyor, 5/18/04 - Not Found - Set stone, 35 links South from Antwerp Township Corner. T.A. Smith, Co.Surveyor, found stone - 4' South CL of Road. J. Stack, Found Stone 11/31/68. W.Q. Smith, Co.Surveyor, 10/13/68-7/15/70, 5/9/73, Found stone, flush with ground & 13'± South of CL of Road, 23.10' South of Antwerp Township Corner, Liber 2, Page 71. D.R. Gilchrist, Co.Surveyor, Found stone with "x" set sign post by corner, 23.12' South of Antwerp Township Corner. Found stone "X" sign post beside, set Harrison Marker. Recorded Liber 3, Pages 246 & 247.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner was field check on 6/22/94 by D.R. Gilchrist, Co.Surveyor. Approved at the 6/29/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Retified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D.R.G. 10/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Harrison Marker
Power Pole South 27.80' PK Nail West Side
Power Pole N 45° W - 64.67' PK Nail West Side
Railroad Tie Fence Post - North - 61.67' PK Nail West Side
24" White Oka - N 45° E - 78.61' PK Nail East Side
18' South of Centerline of Road
23.12' jog South of Antwerp Township Corner
Sign Post 1' South

Signed by Donald R. Gilchrist

Date 9/22/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583