

1933

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 23 8 37 AM '93  
Filing Requirement of Act 74, Mich. P.A. 1970  
County Remonumentation Program

For corners in  
Lawrence Township  
Van Buren County  
(County)

Located In: Corner Code #

*Mark A. Smith*  
VAN BUREN CO  
REGISTER OF DEEDS

- 1. Public Land Survey T 3S R 15W F-13  
S  $\frac{1}{4}$  Post, Section 33. T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Gilchrist in a field survey on July 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 4/1827 - Government Survey - D.S.  
West on South boundary 40.00 ch.  
Section  $\frac{1}{4}$  Section post  
Witnesses: 9" beech - N 21 Deg E - 23 lks. = 15.18'  
7" beech - N 75 Deg 20' W - 51 lks. = 33.66'
- 10/28/1868 - A.J. Pierce, C.S.  
Book 3  
Found both witness trees  
Renewed with iron Stake

(continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Dug hole 15 x 14' x 2.5' found NO evidence  
Set Harrison Marker on line and  
This corner is accepted as a careful and faithful re-establishment of the position of the original corner  
Approved by County Peer Group on 7/28/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Harrison Marker  
Witness post 1' N  
6" sugar - N 95 Deg E - 26.77' to Pk/W in S. face  
20" ash - S 25 Deg E - 51.20' to Pk/W in E. face  
2- 24" ask - S 35 Deg W - 53.55' to Pk/W in W. face  
6" sugar - N 90 Deg W - 61.12' to Pk/W in S. face  
12' N of CL of E&W Rd

Signed by Donald R. Gilchrist  
Donald R. Gilchrist  
Surveyor's Michigan License No. R.L.S. 13583

Date 9/20/93



A Continued from front of Certificate

1903 - J. S. HAINES, C.S.

Stone ?

Witnesses: 7" Elm - N 9 Deg E - 46.5 lks - 30.69'.

6" Cherry - S 23 Deg 30' W - 39 lks. = 25.74'.

7/12/1934 - H. WARD, COUNTY ROAD COMMISSION.

Measured length, South side Section 33 is 5259.5'. Midpoint on Section Line does not check with old fence to North or with following witnesses to South 1/4 Corner.

Witnesses: 7" Elm - N 9 Deg E - 46.5 lks. = 30.69'.

6" Cherry - S 23 Deg 30' W - 39 lks. = 25.74'.

Dug for corner but found no evidence. This location places corner in proper alignment with fence to North, but is 17' West of midpoint on South Section Line. Did not set corner account of conflicting evidence (Calculate 2612.75' West from fence and 2646.75' East from fence).