

FILED

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 34 PM '93

Mark A. Smith
VAN BUREN CO
REGISTER OF DEEDS

For corners in

Van Buren
(County)

Located in:

Corner Code #

Lawrence Twp.

1. Public Land Survey

T 3 S R 15 W

G-3

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3							●					
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James E. Boynton, in a field survey on December 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by U.S. Government Deputy Surveyor William Brookfield, in 1830. Corner used in survey by A.J. Teed in 1873. A.A. Fosdick found stone at corner in 1883; 18" Black Walnut S. 18° W. 31.51k.; angle point in road South 38k. Stone found in 1900 by George Mutchler in 1900. (see over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone from 1973 witnesses: 16" Maple NW. 53.60'; fence post S.E. 36.0'; R.R. tie East 22' to face.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard marker over the stone and cemented into monument box. This corner was ratified by Peer Committee on 10/27/93 as a careful and faithful perpetuation of the original corner. Witnesses: Nail in 24" Maple N.W. 53.64'; Nail in 7" Maple WNW. 46.06'; Nail in P.P. SW. 86.43'; Nail in 6" Elm East 53.38'

Signed by James E. Boynton
Surveyor's Michigan License No. 29239

Date 12-20-93
Page 4 of Page 119
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1988
6856 12/17/93 4.00
REVISED JAN., 1993

The corner was used in numerous surveys from 1946 through 1978, L.C.R.C. in 1973 by Dennis Middleton calls for found monument box over stone.

Label 4 page 120