

FILED

1993

DEC 27 1 34 PM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Van Buren
(County)
Lawrence Twp.

Located In:

Corner Code #

- 1. Public Land Survey T 35 R 15 W ~~G-5~~ G-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Mark A. Smith
VAN BUREN CO
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

665-12/27 0104 105URVEY 9.00

I, James E. Boynton, in a field survey on December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5							●					
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Government set in 1830 by William Brookfield, Deputy Surveyor, witnesses: 16" Beech N. 3°E, 30.1k.; 14" White Ash S. 75°-15'E, 27.1k. W.H. Goss survey in 1900 shows stone and iron, witnesses: Maple NE 38.5'; Maple SE 37.0'. T.A. Smith in 1925 could not find stone, drove iron pipe from old witnesses, witnesses: 20" Maple N. 85°W, 28.3' to E; N.E. Corner of house S. 65°W, 63.5'; E. end headwall S. 88°W, 10.8'; 24" Maple N. 50°E, 40.0' to E; 30" Maple S. 90°E, 39.0' to E. Used in many surveys from 1947 through 1974. LCRC. filed in

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (see over)
Found pinch pipe in monument box from old witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
set standard marker over pipe as directed by Pacer Group on 10/27/93 as best evidence of original corner. Witnesses: P.P. N. 70°W, 31.45' to nail; P.P. N. 45°E, 51.41' to nail; 34" Maple S. 80°E, 65.45' to nail in N. foot; NE. corner house foundation S. 45°W, 63.48'.

Liber 4 page 117

Signed by James E. Boynton
Surveyor's Michigan License No. 29239

Date 12/20/93

A-continued.

1972 by Dennis Middleton shows found pipe as called for in
1925 by T.A. Smith, witnesses: NE. Corner of house S. 65° W.
63.5'; U.P. ~~Maple~~ N. 70° W. 31.73'; 24" Maple N. 50° E. 39.41'; 26"
Maple S. 45° E. 39.48'.

Refer to Page 118