

1993

FILED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SEP 23 8 37 AM '93

For corners in  
Lawrence Township  
Van Buren County  
(County)

Located In:

Corner Code #

*Mark A. Smith*  
VAN BUREN CO  
REGISTER OF DEEDS

1. Public Land Survey	T	R	
SE corner Section 33	T 3S	R 15W	G-13
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Donald R. Gilchrist, in a field survey on July 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4/1827 - Government Survey - William Brookfield, D.S.  
West on South boundary 80 ch. set Post Corner  
Witnesses: 50" cherry - N 60 Deg 20' E - 14 lks = 9.24'  
32" beech - N 69 Deg 30' W - 24 lks. = 15.84'

12/1866 - C.J. Monroe, C.S.  
Book 1  
Found Corners on South line of Section 34  
Measured 39.94 ch. (2636.04') & 39.94 ch. (2636.04') for Total of 5272.08'  
(Continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd Stone & plump top set by W.H. GOSS  
SL Fd by Homer Ward, Co. Rd. Eng. Ward's witnesses ck.  
Approved on 7/28/93 by County Peer Group Meeting  
This corner is accepted as a careful & faithful perpetuation of the original Section corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker  
20" Hemlock - N 15 Deg W - 44.16 to Pk/W E. face  
22" ash - N 60 Deg E - 56.96 to Pk/W S. face  
P.P. - S 80 Deg W - 88.48 to Pk/W N. face  
36" R.Oak - S 60 Deg 30' E - 95.47 to Pk/W S. face  
Jog 104.4' E to NE corner Section 4 Hamilton Township 4' N of CL E&W Rd and on CL Rd N

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by *Donald R. Gilchrist*  
Surveyor's Michigan License No. R.L.S. 13583

Date 9/20/93



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, MAY 28, 1971  
REVISED JAN. 14, 1975  
3401 09/23 0104 10SURVEY

*Label 4 Page 42*

A. Continued from front of Certificate

10/28/1868 - A. J. PIERCE, C.S.

Book 3

Found both witness trees.

Renewed witnesses and stake.

4/20/1871 Stake present, renewed, both witnesses down, roots remain & agreed well.

Measured North 19.88 ch. (1312.08') to 1/8 Post & continued North 19.88 ch. (1312.08') to 1/4 Post for Total of 2624.16'.

1903 - J. S. HAINES, C.S.

Found a stone at 1/8 Post to North.

Measured North to 1/4 Post 19.95 ch. (1316.70').

No Date - W. H. GOSS, C.S.

Set Corner from Hamilton Corner.

Set Pump Top, Stake & Stone.

Witnesses: 13 " Walnut - S 33 Deg 15' E - 2.36 ch. = 155.76'.

21" Walnut - S 82 Deg 15' W - 3.305 ch. = 218.13'.

7/12/1934 - H. WARD, COUNTY ROAD COMMISSION.

Note.

Found Well Pump Casting surrounded with collar of stones. 4" below surface.

Witnesses : Corner of Stone foundation on House - N 41 Deg 15' W - 105.5' (see witness note).  
10" Ash - N 60 Deg E - 58.0' to Center Line.  
6" Walnut - N 75 Deg E - 108.0' to Center Line.  
8" Ash - S 75 Deg 30' E - 127.7' to Center Line.  
20" Red Oak - S 63 Deg 30' E - 94.7' to Center Line.

6" Walnut - S 47 Deg E - 123.6' to Center Line.

Corner is 104.3' West of Hamilton Corner.

6/15/1992 - J. C. HUNT, P.S.

Recorded Survey (L9-P333)

Found Stone with "x" & small stones & irons around it.

In line with Center Line of Road North.

4' North of Center Line of Road E&W.

Set Iron with cap, South 33.0'.

Witnesses: 20" Pine - N 15 Deg W - 43.67' (nail in East face).

22" Walnut - N 60 Deg E - 57.37' (nail in South face).

Pole - S 80 Deg W.

East - 104.78' to 1/2" iron. NE Corner Section 4-4-15.

*Index 4 page 43*