

NOV 15 1994

NOV 4 4 11 PM '94

LIBER 4061517N

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Hartford Township

Van Buren County (County)

Located In:

Corner Code #

Mark A. Smith VAN BUREN CO. REGISTER OF DEEDS

7-00

- 1. Public Land Survey T 3S R 16W C-11 SE Corner Sec 30 T R T R T R
2. Property Controlling in Section S T R S T R
3. Miscellaneous Property in Sec. S T R S T R

Register of Deeds Stamp & File Number

11/04 0101 10SURVEY

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 11, column C.

I, Donald R. Gilchrist, in a field survey on 11/2/94, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1830 Gov. set post: 14" Sycamore N 88° W 22 lks.; 12" Beech S 82° E 36 lks. In 1868 A.J. Pierce, CS, used cor. to set E 1/4 post of Sec. 30. On Apr. 10, 1870, he noted stake reset - 1 wit. stump removed, put down good stake. In the 1940's & 50's T.A. Smith, CS, noted pipe. On June 19, 1980 Gove Assoc. fd. 6" pipe over stone. In 1980's Mitchell notes 1" pipe. On June 23, 1992 J.C. Hunt fd. 3/4" I.P. 1.5' S of C/L of road as G. Mitchell had noted. Hunt survey recorded in Liber 9 pg. 347. At meeting of Peer Group on Oct. 21, 1992, approval was given to re-set corner. On Oct. 22, 1992, fd. 3/4" I.P. 1.5' S of C/L road as noted above. Removed I.P. & set Harrison Marker.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


10/18/94 D.R. Gilchrist, C.S., fd Harrison Marker paved over last year. Set mon. box over. Approved at the 11/2/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date 11/4/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Fd. Harrison Marker, set Mon. Box over. N 03° E 32.1' C/L tel. cable box N 02° W 49.42' Pk W. face 3" dia. tree N 45° W 42.61" W end 15" dia. C.M.P. N 80° W 160.45' nail S face pole. 2' S of CL rd Measured dist W 2634.08' Measured dist E 2651.02'



Signed by Donald R. Gilchrist

Date 11/4/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583