

SURVEY & REMONUMENTATION

FILED

VAN BUREN COUNTY REMONUMENTATION PROGRAM

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE **DEC 21 3 43 PM '94**
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

VAN BUREN
(County)

Located in:
HARTFORD TWP.

Corner Code #

Maule Smith
 VAN BUREN CO.
 REGISTERED LAND SURVEYOR

1. Public Land Survey Sec. 4 T 3 S. R 16 W. F-3
 S $\frac{1}{2}$ Post T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 231

Register of Deeds Stamp & File Number

7-00
12/21 0101 105URVEY 9394

I, John C. Hunt, P.S., in a field survey on Nov. 23, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-3 GOV.: Wm. Brookfield DS, Set $\frac{1}{2}$ sec. post on corrected line 40.015 chs. Wit.: 14" Sugar Maple N56°E 7 lks, 12" Sugar Maple S88°W 15 lks. 7/2/1869 AJ Pierce DCS, Bk. 3 p.83: Dug & fd. old stake & stone. 4/11/1874 AJ Teed CS, Bk. 4 p.153: Fd. stake by. No date, maybe Goss: Red Bk.: Stone, Wit.: 14" Sugar Maple S. 44.5 lks. 12/23/1952 WQ Smith CS, Map shows cor., dist. E. 1327.05' to 1/8 post. On 5/8/1958 he shows on map & notes: Fd. iron pipe in line w/ fence N. Distance E. 1327' to $\frac{1}{2}$ post & cont. E. 1327' to sec. cor., total 2654'; Wit.: 30" Maple S. 30'. 6/23/1967 Map shows cor. 11/28/1990 JC Hunt PS, Rec. Cert. L.3 p.176: Fd. 3/4" iron pipe in monument box, Wit.: N3°E 21.40' PK nail W. root 13" Maple, N65°W 40.30' PK nail NE face twin 12" tree, S5°E 27.57' PK nail NE root 36" Maple, S60°W 48.07' PK nail NE root 36" Maple.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3 Corner common to sections 4 & 9, T3S-R16W, Hartford Township.
 Corner evidence found: Found 3/4" iron pipe and brick in monument box. Removed and set Slim-Line Harrison Marker in monument box 3.5' North of centerline of road East & West (C.R. 372). Corner is in line with fence and brush row to North.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPORVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON NOVEMBER 2, 1994, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Validated by Peer Group in accordance with P.A. 345 of 1990
 Van Buren County Surveyor

Date J. R. G. 12/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 SLIM-LINE HARRISON MARKER IN MONUMENT BOX

- N.03°E. 28.33' Set PK nail & washer in E. face of 4" Maple.
- S.07°E. 29.30' Set PK nail & washer in E. root of 38" Maple
- S.52°W. 49.02' Set PK nail & washer in N. base of 30" Maple.
- N.63°E. 49.72' Set PK nail & washer in S. face of 14" Maple.

Signed by John C. Hunt
 Surveyor's Michigan License No. 23513

Date Dec. 15, 1994

