

**SURVEY &
REMONUMENTATION**

FILED

APR 25 1995

DEC 6 1 47 PM '94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Hartford Township

Van Buren County
(County)

Located In:

Corner Code #

Mark A. Smith
VAN BUREN CO.
REGISTERED PROFESSIONAL SURVEYOR

1. Public Land Survey	T	³⁵ R 16W	<u>F-13</u>
S 1/4 Sec. 33	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald R. Gilchrist a field survey on November 18, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

See History on Reverse Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FD No Corner - Set Slimline Harrison Marker in Mon Box
Set Corner on line from SW Corner, Section 33, Hartford Twp, thru N1/4 Post Section 4, Keeler at the Jog Dist. of 93.06 feet
Approved at 11/2/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful re-establishment of the position of the Original Government Corner.

Validated by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date D. R. G. 12/6/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Slim Harrison Marker in Mon Box
5" Elm - S - 29.78' pk/w E. Side
8" Elm - S40°E - 48.15' pk/w NE Side
4" Elm - S55°W - 55.40' pk/w NW Side
1' S of centerline
Jog 93.06' West



Signed by Donald R. Gilchrist Date 12/5/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 15
8904 12/06 0104 10 SURVEY 9-00 REVISED MAY 14, 15
REVISED JAN. 15

Like 4 page 206

**South Quarter Post of Section 33,
Town 3 South, Range 16 West, Hartford Township.**

4/1827 - GOVERNMENT - William Brookfield, D.S.

West on South boundary of Section 33 a distance of 30.00 chs. (1980.00'), Stream is 10 lks. (6.60') wide with a course of Northeast, continued West for a total of 40.00 chs. (2640.00') and set Quarter Section Post.

Witnesses:

6" Elm - N 12 Deg E - 39 lks. (25.74').

6" Linden - N 5 Deg 30' W - 11 lks. (7.26').

Jog at Southwest Corner is 1.4 chs. (92.40') West to Keeler Township Corner. Jog at Southeast Corner is 1.42 chs. (93.72') West to Keeler Township Corner.

8/1900 - George Mutchler, C.S.

Book 6 - Page 48 (Survey in Section 4 of Keeler Township).

Does not show North Quarter Post.

Measured East 19.91 7/8 chs. (1314.56') to Eighth Post and continued 1314.56' to Northeast Section Corner (Plow Point).

Measured West 39.83 3/4 chs. (2629.11') to Northwest Corner (Stake and Stone).

Measured South 13.71 chs. (904.86') to eighth Post, and continued South 20.05 chs. (1323.30') to Center Quarter Post (Iron Pipe).

11/1988 - John C. Hunt, P.S.

Recordation Certificate for Southwest Corner of Section 33 (Liber 3 - Page 117).

10/19/1993 - Van Buren County Peer Group.

Recordation Certificate for Southeast Corner of Section 33 (Liber 4 - Page 63).

