

1993

FILED

COMMISSION

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE Oct 19 11 52 AM '93

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 54

For corners in

<u>Van Buren</u> (County)	Located In: <u>Hartford Twp.</u>	Corner Code # <u>G-9</u>
1. Public Land Survey	Sec. 21 T 3 S. R 16 W.	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Mark A Smith*  
VAN BUREN CO  
REGISTER OF DEEDS

7.00  
10/17 0101 10SURVEY

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S., in a field survey on July 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Jan. & Feb. 1830 Gov. Survey: Wm. Brookfield DS: North 80.00 ch, Set post sec. cor., 24" Sycamore N.76°30'E. 12 lks., 11" Beech N.65°W. 65 lks. ? 11/10/55 TA Smith CS: notes a point at this corner. 11/13/71 E. Stepan RLS, Fd. iron in mon box. 9/20/75 JC Hunt PS: Used corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Section corner common to Sections 21, 22, 27, & 28, T3S-R16W, Hartford Township. Corner evidence found: On July 28, 1993, found Standard marker in monument box in C/L C.R. 687. No Harrison Marker set. Corner accepted and approved as found.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON MAY 26, 1993, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 STANDARD MARKER IN MONUMENT BOX

- West 58.20' Spike in N. face of pole.
- East 27.30' & 37.08' C/L of 4" steel post filled & set in concrete.
- N.50°W. 42.37' PK nail in SW face of pole.
- S.28°E. 55.92' PK nail in SW face of pole.



Signed by *John C. Hunt*  
Surveyor's Michigan License No. 23513

Date Oct. 17, 1993