

1933

VAN BUREN COUNTY REMONUMENTATION PROGRAM

AUG 20 3 26 PM '93

COMMISSION:

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mari A. Smith
VAN BUREN CO
REGISTER OF DEEDS

For corners in

VAN BUREN
(County)

Located In:

Corner Code #:

HARTFORD TWP.

LIBER 4 PAGE 31

- 1. Public Land Survey Sec. 34 T3 S. R 16 W. G-12
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John C. Hunt, PS, in a field survey on July, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5/18/1830 GLO Wm. Brookfield DS: N. bet. Sec. 33 & 34 set 1/4 post at 40 ch.; Wit.: 11" Beech S.67°W. 6 lks. (40.26'), 11" Lynn N.40°E. 32 lks. (21.12'). 11/10/1955 W.Q. Smith CS, notes show a point; meas. N. 1317.27' to fence line on W. & cont. N. 1316.89' to Sec. cor. for total of 2634.16'. (See copy of notes Section Corner information)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Quarter Post common to Sections 33 & 34, T3S-R16W, Hartford Township.
Corner Evidence Found: Nothing

July 19, 1993, set Harrison Marker as per Peer Group approval on June 30, 1993, in C/L road North & South and in line with fence to East. On July 28, 1993, found Monument Box over Harrison Marker. See sketch on back for corner location.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 30, 1993, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G12 MONUMENT BOX OVER HARRISON MARKER

- S.87°W. 56.92' PK nail in top of wood post.
- S.25°W. 91.87' PK nail East face pole.
- S.40°E. 48.50' PK nail SW face 9" Pine tree.
- East 35.37' PK nail NW corner RR tie post.



Signed by John C. Hunt, P.S.

Date August 16, 1993

Surveyor's Michigan License No. 23513

G-12

SKETCH OF CORNER COMMON TO SECTIONS 33 & 34, T35-R16W

SEC. 28

SEC. 27

SEC. 33

SEC. 34



NO SCALE.

SEC. COR. COMMON TO SECTIONS 27, 28, 33 & 34, T. 35.-R. 16W.

2632.51'

MEAS.

179°-24'-35"

2635.207'

MEAS.

1/4 POST COMMON TO SECTIONS 33 & 34, T. 35.-R. 16W.

SECTION COR. COMMON TO SECTIONS 33 & 34, T. 35.-R. 16W, ON TOWN LINE

93.72'

SECTION CORNER COMMON TO SEC. 3 & 4, T. 45.-R. 16W, ON TOWN LINE.

SEC. 4

SEC. 3

SURVEY & REMONUMENTATION

AUG 26 1993

COMMISSION