

1993

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 19 11 52 AM '93

LIBER 4 PAGE 63

For corners in

<u>Van Buren</u> (County)	Located In: Hartford Twp.	Corner Code # G-13
1. Public Land Survey Sec. 34	T 3 S. R 16 W.	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Mark A. Smith
VAN BUREN CO
REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	5		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, John C. Hunt, P.S., in a field survey on July 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5/1830 Gov. Survey, Wm. Brookfield DS: W.80 ch on S. boundary of Sec. 34, set post cor. to Sec 33 & 34; Wit.: 20" Beech N.85°E. 27 lks., 7" Beech N.32°W. 50 lks. 12/20/1872 AJ Pierce CS Survey in Bk. 4 pg. 109 & 155: NW cor. Sec. 3 Keeler Twp. was est. on line bet. sec. cor. 1 mi. W. & NE cor. of Sec. 3, & at intersection of SW cor. of Sec. 3 through W 1/4 post. Set temporary stake & guides 1 rod N&S to be made permanent when thawed out. Meas. E. from sec. cor. 40.48 ch (2671.68') to 1/4 post & cont. 40.48 ch to sec. cor. for total of 5,343.36'. From W 1/4 post of sec 3 meas. N.34.26 ch (2254.56'). Gov.: 34.14 ch = 2253.24'. Present cor. agrees well w/ rd fences. Jog is 1.42 ch (93.72') E. to Hartford Twp. cor. 8/3/1900 G Mutchler CS: Survey in Sec 4 Keeler Twp.: NE cor., fd. plow point, no wit. remain. Re-wit. by 12" Hickory N.34°45'E. 184.1 lks. (121.77'). Meas. W. 19.91 7/8 ch (1314.59') & set stake; cont. W. 19.91 7/8 ch (1314.59')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (Continued on back)

G-13 Section corner common to Sections 34 & 35, T3S-R16W, Hartford Township, on Township Line. Corner evidence found: 3/4" Iron Pipe 10" deep w/ nail & cap over, 4.5' S. of C/L of road E. W. (72nd Ave.) & 82.72' E. of C/L C.R. 687. On July 19, 1993, set Harrison Marker, and on Aug. 12, 1993, Monument Box over Harrison Marker. THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PANEL GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 30, 1993, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 HARRISON MARKER IN MONUMENT BOX

- West 93.72' Harrison Marker
- S.75°W. 127.71' PK nail in SW face of pole.
- N.25°W. 35.22' Nail & tag in top of wood post by tel. cable box.
- S.82°E. 139.83' Nail & tag in N. face of pole.
- N.75°W. 124.20' C/L of GTE manhole.

Signed by John C. Hunt, P.S.
Surveyor's Michigan License No. 23513

Date Oct. 17, 1993



LIBER 4 PAGE 63

(Continued from front)

to $\frac{1}{4}$ post for a total of 2629.18'.

1900+ WH Goss CS: Well filter & brick. Wit.: 14" Hickory NW 1.54 lks. (101.64'), 3" Walnut SW
.79 lks. (52.14')

1930+ TA Smith CS: Ran sec. line S. from $\frac{1}{4}$ post common to sec. 33 & 34 to a P.O.T. nail at 1168'
continuing S. 150' to a pipe (?), continuing S. 1315.75' & witnessed a point. Crew was to look
for plow point 93.72' West.