

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>14</u>	T. <u>4</u> S., R. <u>13</u> W.	<u>K-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>4</u> S., R. <u>13</u> W.	<u>K-5</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, D. Scott do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Feb 3 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Feb. 3 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

*Recovered 1/2" Iron Pipe. Corner is part of Survey by T.A. Smith of Paw Paw, Michigan.
 Raised corner with 1" Iron pipe and placed Plastic Cap with #12029 on top of pipe*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Iron Pipe with Plastic Cap #12029

*S. 1-00' E. 34.60' 6" Maple
 N. 74-00' E. 56.20' 8" Basswood (one of clump)
 N. 43-30' W. 33.46' 28" Black Cherry*

All distances to PK. Nails in base of trees

SIGNED BY _____ DATE 2-3-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12029 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____