

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSIONING Requirement of Act 74, Mich. P.A. 1970

For corners in

Van Buren

(County)

Located In:

Corner Code #

Porter Township

S.E. corner Sec. 13

- | | | | | | | | |
|--------------------------------------|---|---|---|---|----|---|-----|
| 1. Public Land Survey | T | 4 | S | R | 13 | W | M-7 |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Section | S | | T | | R | | |
| | S | | T | | R | | |

FILED

DEC 29 4 28 PM '95

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Lemke, in a field survey on May 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1827: United States Government Survey; set post common to Section 13 & Section 24 on Township line.
Hickory 8" S. 54 $\frac{1}{2}$ ⁰ W. 33 links
Beech 22" N. 65 3/4⁰ W. 34 links
- 1829: United States Government Survey; line between Sections 18 & 19, T. 4 S., R. 12 W. intersect town line 36 links North of post. Set post at intersection.
Beech 24" N. 21⁰ E. 38 links
Beech 9" S. 72⁰ E. 19 links
- 1905: Van Buren County Records Pg. 37; reads "Stone from Kalamazoo corner".
Elm 24" N. 44 $\frac{1}{2}$ ⁰ E. 89 links Apple 20" S. 51 $\frac{1}{2}$ ⁰ E. 86 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We dug approximately 6' x 2' x 4' deep at each corner. A drilled stone was found at the Kalamazoo corner, a group of stones with no discernible markings were located at the Van Buren corner.



Ratified by Peer Group in accordance with P.A. 345 of 1998
Van Buren County Surveyor

Date 2-15-95 *S. P. A.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Northeast corner Section 24, T. 4 S., R. 13 W., ratified by the Van Buren County Remonumentation Peer Group on February 15, 1995. Found stones as detailed in Section B of this form. This monument is accepted as a careful and faithful perpetuation of the position of the original corner. Removed stone and placed 20" Harrison Monument in its place with a Monument Box over.

- Center line "W" Avenue North 21'
60 d spike (@ ground) in Power Pole N. 34⁰ W. 114.40'
Nail/Tab in E. side Power Pole N. 24⁰ E. 91.48'
PK Nail in W. side (2.5' above ground) 18" Elm N. 62⁰ E. 122.19'
PK Nail in N. side (3' above ground) Power Pole S. 80⁰ E. 124.09'

Signed by *Robert E. Lemke*

Date 12/28/95

Surveyor's Michigan License No. 40160